

SURVEY & REMONUMENTATION

MAY - 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Washtenaw

(County)

Located In:

Corner Code #

- | | | | | | |
|---------------------------------------|---------|-------------|-------------|--|-------------|
| 1. Public Land Survey | | T <u>1S</u> | R <u>4E</u> | | <u>I-10</u> |
| | | T _____ | R _____ | | _____ |
| | | T _____ | R _____ | | _____ |
| | | T _____ | R _____ | | _____ |
| | | T _____ | R _____ | | _____ |
| 2. Property Controlling
in Section | S _____ | T _____ | R _____ | | _____ |
| | S _____ | T _____ | R _____ | | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ | T _____ | R _____ | | _____ |
| | S _____ | T _____ | R _____ | | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED
 WASHTENAW COUNTY, MI
 DEC 1 11 25 AM '94
 PEGGY M. HAINES
 COUNTY CLERK/REGISTER

LIBER. 1 PAGE 118 RM
- COPY -
Register of Deeds Stamp & File Number

I, R. Timothy Tietsema, in a field survey on April 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
1819	GLO (Wampler)			Fld. Notes	Set Original Corner Set 1/2 mile post	1) 22" W. Oak N05E 100 links(66.00') 2) 22" W. Oak N45W 80 links(52.80')
11/19/1934	W. J. Armstrong			Resurvey	Fnd. old wood stake replaced with 1 1/2" Iron Pipe, bricks.	3) 6" R. Oak N01E 53.4' 4) 30" W. Oak N56E 63.8' 5) 3" Elm S75E 97.3' 6) 6" Walnut N62W 71.2'
6/19/1972	Oscar Boss	13574	L2P109		Found 2" Pipe	3) 18" Maple N10E 53.36' 7) 10" Locust N33W 68.35' 8) 14" Locust S85W 78.47'

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In April of 1994, LSC found a 1 1/2" iron pipe using these witnesses:

Fnd. 1 1/2" Iron Pipe	3) 20" Oak	N03E	53.5'
6' S. Centerline Fleming Rd.	4) 39" Oak	N57E	64.3'
12' E. Centerline McGuiness (no brick found).	6) 22" Walnut	N64W	71.1'
	7) 10" Locust	N33W	68.35'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

April 20 1994	R. T. Tietsema	20712	Remon.	Fnd. 1 1/2" Iron Pipe Added a Wash. Co. Remon. Cap.	3) 22" Oak N05E 53.44' to nail & R.T. 4) 48" Oak N70E 64.30' to nail & R.T. 6) 18" Walnut N60W 71.10' to nail & R.T. 7) 14" Walnut N25W 68.54' to nail & R.T.
---------------	----------------	-------	--------	---	--

It is our opinion that this corner represents the original corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by R. Timothy Tietsema Date May 6 1994
 Surveyor's Michigan License No. 20712

CONTINUED FROM A. ON FRONT:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES		
4/21/1979	Charles C. Wilson	13604	L5P257		Fnd. 1 1/2" Iron Pipe	3) 20" Oak	N03E	53.5'
						4) 39" Oak	N57E	64.3'
						6) 22" Walnut	N64W	71.1'
						8) 15" Walnut	S82W	78.4'
8/20/1984	N. N. Fahrner	17620	L7P90		Fnd. 1 1/2" Iron Pipe	3) 18" R. Oak	N01E	53.40'
						4) 36" Oak	N56E	64.30'
						6) 18" Walnut	N62W	71.10'
						9) Road Sign	S45W	16.5'
10/29/1985	N. N. Fahrner	17620		Boundary	Fnd 1 1/2" Iron Pipe	3) 20" Oak	N03E	53.5'
						4) 39" Oak	N57E	64.3'
						6) 22" Walnut	N64W	71.1'
						8) 15" Walnut	S82W	78.4'
Jan 1989 & Mar. 1990	R. T. Tietsema Job No: 22287	20712		Boundary	Fnd. 1 1/2" Iron Pipe	3) 20" Oak	N03E	53.5'
						4) 39" Oak	N57E	64.3'
						6) 22" Walnut	N64W	71.1'
						8) 15" Walnut	S82W	78.4'

APPROVED
DATE 5/3/94
CO. REP. K

7

