

**SURVEY &
REMONUMENTATION**

RECORDED
WASHTENAW COUNTY, MI

MAY - 1 1995

Dec 1 11 26 AM '94

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Washtenaw

PEGGY M. HAINES
COUNTY CLERK/REGISTER

-COPY-

(County)	Located In:	Corner Code ##
1. Public Land Survey	T 1S R 4E	L-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

-IBER 1 PAGE 122.RM
-COPY-

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	16	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, R. Timothy Tietsema, in a field survey on April 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
1819	GLO (Wampler)			Fld. Notes	Set Original Corner Set 1/2 mile post.	1) 24" W. Oak N66W 7 links(4.62') 2) 12" B. Oak S44W 25 links(16.50')
Unknown	Atwell Hicks				Set Axle Shaft w/ gear on top.	3) N & S Fence EAST 12.2' 4) 4"-6" Box Elder N15E 38.3' 5) 8"-12" Forked Oak S45E 19.7' 6) 4" Oak S40E 22.3' 7) 6" Oak S20E 38.8' 8) 4" Cherry S19E 39.6'

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In April of 1994, LSC found a 1" Axle Shaft using these witnesses:

- 3) Fence Post EAST 12.0'
- 4) 18" Multi. Box Elder N10E 38.0'
- 5) 24" Tw. Oak EAST 19.55'
- 8) 4" Cherry S19E 39.6'
- 9) 4" Box Elder EAST 6.05'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

April 20 1994	R. T. Tietsema	20712	Remon.	Fnd. 1" Axle Shaft 0.5' above surface	3) N-S Fence EAST 11.8' 4) Dead Box Elder N30E 38' 5) 28" Tw. Oak S55E 19.03' to nail & R.T. 8) 14" Cherry S15E 39.51' to nail & R.T. 9) 10" Oak N80E 6.19' to nail & R.T. 10) 8" Oak S10W 24.35' to nail & R.T.
---------------	----------------	-------	--------	------------------------------------------	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

It is our opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

Signed by R. Timothy Tietsema Date May 6 1994
Surveyor's Michigan License No. 20712

-LIBER

1 PAGE 1231

- copy -

CONTINUED FROM A. ON FRONT:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
1/8/1972	Glenn Richard	13040	L1P449		Fnd. 1" Axle Shaft w/ gear on top as established by Atwell Hicks.	4) 4"-6" Box Elder Clump N15E 38.0' 5) 8"-12" Forked Oak S45E 19.49' 6) 4" Oak S40E 22.37'
8/25/1976	N. N. Fahrner JOB NO: 14451	17620		Boundary		No Witnesses given.
12/27/1977	N. N. Fahrner JOB NO: 15160	17620		Boundary		No Witnesses given.
8/2/1978	N. N. Fahrner JOB NO: 15948	17620		Boundary	Fnd. 1" Axle Shaft	3) Fence Post EAST 12.0' 4) 18" Multi. Box Elder N10E 38.0' 5) 24" Tw. Oak EAST 19.55' 9) 4" Box Elder EAST 6.05'

APPROVED

DATE 5/3/74

CO. REP. M

7

