

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 124
- Copy -
DEC 1 11 26 AM '94
RECORDED
WASHTENAW COUNTY, MI
PEGGY H. HAINES
COUNTY CLERK/REGISTER

For corners in COMMISSION
Washtenaw
(County)

	Located In:	Corner Code #	
1. Public Land Survey	T <u>1S</u> R <u>4E</u>	<u>I-13</u>	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, R Timothy Tietsema, in a field survey on May 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
1819	GLO (Wampler)			Fld. Notes	Set Original Corner Set post for the cor. of Sections 34 & 35. 4.60 chains (303.60') East of Corner between Sections 2 & 3, T2S, R4E, Lima Twp.	1) 20" W. Oak EAST 57 ⁶ / ₁₀ links (380.16') 2) 24" W. Oak S10W 275 links (181.50')
Sept 1936	W. J. Armstrong	W.C.R.C.		Resurvey	Fnd old rotted end post in the muck. Set 1 1/2" x 36" Iron pipe, stones and brick.	3) 3" Elm N05E 68.6' 4) 8" Elm N25E 54.9' 5) 5" Elm N40E 53.5' 6) 5" Tw. Elm N75W 103.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In May of 1994, LSC found a 1 1/2" Iron pipe using these witnesses:

Fnd 1 1/2" Iron Pipe w/stone & brick @ SW cor. of Maple Hardwood swamp @ fence line int. E-W & N.	7) 12" Maple N05E 45.9'
	9) 6" Willow S75W 9.4'
	10) 5" Willow WEST 50.3'
	11) SW Cor. Fnc. Post N10E 1.1'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

May 18 1994	R. T. Tietsema	20712	Remon.	Fnd 1 1/2" Iron Pipe w/stone & brick @ SW cor. of Maple Hardwood swamp, @ fence line int. E-W & N.	7) 15" Maple NORTH 45.96' to nail & R.T. 9) 16" Tw. Willow S75W 8.67' to nail & R.T. 10) 12" Tw. Willow WEST 56.67' to nail & R.T. 11) SW Cor. Fnc Post N10E 1.1' to nail & R.T. 12) Consumers Power EAST 35.83' to center of post Underground Gas Line Marker.
-------------	----------------	-------	--------	--	---

It is our opinion that this corner represents the original corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by R Timothy Tietsema Date October 3, 1994
Surveyor's Michigan License No. 20712

1

-LIBER

1 PAGE 12!
-copy-

CONTINUED FROM A. ON FRONT:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
1967 ?	Hand Written Additions in Witness Book with check marks by witness numbers 3-6 (four Elm trees).				Fnd. at E-W Fence line & fence line N'y.	7) 6" Maple N05E 46.4' 8) 4" Triple Elm N60E 48.8'
8/25/1976	N. N. Fahrner JOB NO: 13907	17620	L4P245		Fnd. Iron Pipe	7) 12" Maple N05E 45.9' 9) 6" Willow S75W 9.4' 10) 5" Willow WEST 50.3' 11) SW Cor. Fnc. Post N10E 1.1'
8/2/1978	N. N. Fahrner JOB NO: 15948	17620			Fnd. 1 1/2" Iron Pipe	7) 12" Maple N05E 45.9' 9) 6" Willow S75W 9.4' 10) 5" Willow WEST 50.3' 11) SW Cor. Fnc. Post N10E 1.1'
12/21/1989	Lawrence O'Donell JOB NO: 15948	28419			Fnd. 1 1/2" Iron Pipe	7) 12" Maple N05E 45.9' 9) 6" Willow S75W 9.4' 10) 5" Willow WEST 50.3' 11) SW Cor. Fnc. Post N10E 1.1'

APPROVED

DATE 6/13/94

CO. REP. [Signature]

7

