

SURVEY & REMONUMENTATION

MAY - 1 1995

LIBER

1 PAGE 126 RM

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Washtenaw

County	Located In:	Corner Code #	
1. Public Land Survey	T 1S R 4E	J-9	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

LIBER
 - Copy -
 PEGGY M. HAINES
 COUNTY CLERK/REGISTRAR
 WASHTENAW COUNTY, MI
 Dec 1 11 26 AM '94
 RECORDED
 WASHTENAW COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, R. Timothy Tietsema, in a field survey on April 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
1819	GLO (Wampler)			Fld. Notes	Set Original Corner Post @ average Distance	1) 10" B. Oak N13W 54 links(35.64') 2) 12" B. Oak S31E 62 links(40.92')
Unknown	W. C. R. C.			Resurvey		3) 26" B. Oak N25 1/4E 0.77 ch. (50.82')
10/2/1972	Donald W. Ross JOB NO: 72-903	19005		Boundary	Fnd. Iron	No Witnesses given.

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In April of 1994, LSC found a 1 1/2" Iron pipe using these witnesses:

Fnd 1 1/2" Iron Pipe @ int. fences N, S, E & W (E-W fenceline no longer visible).	4) 20" Oak	S40E	14.4'
	5) 14" R. Oak	S30E	30.15'
	6) 4" Cedar	S70W	13.8'
	7) 6" Cherry	N40W	3.9'
	8) 22" Stump	N25W	5.7'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

April 20 1994	R. T. Tietsema	20712	Remon.	Fnd. 1 1/2" Iron Pipe @ int. fences N, S, E & W (E-W fenceline no longer visible).	4) 22" Oak S40E 13.73' to nail & R.T. 5) 16" Oak S30E 30.18' to nail & R.T. 6) 4" Cedar S50W 13.75' to center 7) 10" Cherry N35W 3.85' to nail & R.T. 8) Stump N35E 5.6' to fnd. nail & washer (Stump about to fall over and disintegrate)
---------------	----------------	-------	--------	--	--

It is our opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

Signed by R. Timothy Tietsema Date October 3, 1994
 Surveyor's Michigan License No. 20712

1

851-8 317

LIBER

1 PAGE 127

-copy-

CONTINUED FROM A. ON FRONT:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
1/8-21/1975	John L. Snyder	13352	L4P127		Fnd 1 1/2" Iron Pipe @ int. fences N, S, E & W.	4) 20" B. Oak S40E 14.4' 5) 14" R. Oak S30E 30.15' 6) 4" Cedar S70W 13.8' 7) 6" Cherry N40W 3.9' 8) 22" Stump N25W 5.7' MSPC Sys. 317,579.46(N)/2, 108,791.51(E).

APPROVED

DATE 7/11/94

CO. REP. [Signature]

7

