

SURVEY & REMONUMENTATION

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 128
- Copy -
Dec 1 11 26 AM '94
RECORDED
WASHTENAW COUNTY, MI
PEGGY M. HAINES
COUNTY CLERK/REGISTRAR

For corners in **COMMISSION**

Washtenaw (County)	Located In:	Corner Code #
1. Public Land Survey	T 1S R 4E	J-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, R Timothy Tietsema, in a field survey on April 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
1819	GLO (Wampler)			Fld. Notes	Set Original Corner @ average distance.	1) 20" B. Oak S46E 97 links(64.02') 2) 16" W. Oak N20W 103 links(67.98')
Unknown	H. H. Atwell (W.C.R.C)			Resurvey	4" Monument	No Witnesses given
7/18/1972	N. N. Fahrner JOB NO: 8682	17620	L2P143	Boundary	Fnd. 1 1/2" Iron Pipe	3) 24" R. Oak S85W 9.3' 4) 12" Tw Hickory S50W 13.2' 5) 18" Sassafras S20W 41.2'

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In April of 1994, LSC found a 1 1/2" Iron pipe using these witnesses:

Fnd 1 1/2" Iron Pipe	3) 36" Oak	S71W	9.12'
30" long surrounded by stones @ base of old wood fence corner post.	4) 15" Tw. Hickory	S32W	12.32'
	5) 18" Sass.	S20W	41.2'
	6) 6" Oak	S12E	40.38'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

April 20 1994	R. T. Tietsema	20712	Remon.	Fnd. 1 1/2" Iron Pipe	3) 36" Oak	S75W	9.30' to nail & R.T.
				30" long surrounded by stones @ base of old wood fence corner post.	4) 18" Tw. Hickory	S30W	12.35' to nail & R.T.
					5) Sassafras Stump	S15W	41.22' to nail & R.T.
					6) 6" Oak	S20E	40.36' to nail & R.T.
					7) 24" Tw. Ash	S10W	49.79' to nail & R.T.

It is our opinion that this corner represents the original corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by R Timothy Tietsema Date October 3, 1994
Surveyor's Michigan License No. 20712

881-8

CONTINUED FROM A. ON FRONT:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
8/25/1976	N. N. Fahrner JOB NO: 13907	17620		Boundary	Fnd. 1 1/2" Iron Pipe	3) 24" R. Oak S85W 9.3' 4) 12" Tw Hickory S50W 13.2' 5) 18" Sassafras S20W 41.2'
10/14/1976	N. N. Fahrner JOB NO: 14451	17620		Boundary	Fnd. 1 1/2" Iron Pipe	3) 24" Red Oak S85W 9.3' 4) 12" Twin Hickory S50W 13.2' 5) 18" Sass. S20W 41.2'
12/27/1977	N. N. Fahrner JOB NO: 15160	17620		Boundary	Fnd. 1 1/2" Iron Pipe	3) 24" Red Oak S85W 9.3' 4) 12" Twin Hickory S50W 13.2' 5) 18" Sass. S20W 41.2'
12/21/1989	N. N. Fahrner JOB NO: 22752	17620		Boundary	Fnd. 1 1/2" Iron Pipe	3) 24" Red Oak S85W 9.3' 4) 12" Twin Hickory S50W 13.2' 5) 18" Sass. S20W 41.2'
August 1991	R. T. Tietsema JOB NO: 07191 JOB NO: 10491	20712		Boundary	Fnd 1 1/2" Iron Pipe	3) 36" Oak S71W 9.12' 4) 15" Tw. Hickory S32W 12.32' 6) 6" Oak S12E 40.38'

APPROVED
DATE 5/3/94
CO. REP. A

7