

**SURVEY &
REMONUMENTATION**

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Washtenaw <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>1S</u> R <u>4E</u>	<u>I-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, R. Timothy Tietsema, in a field survey on April 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
1819	GL.O (Wampler)			Fld. Notes	Set Original Corner	1) 10" W. Oak N80E 26 links(17.16') 2) 10" W. Oak N10W 17 links(11.22')
8/8/1936	W. J. Armstrong			Resurvey	Fnd stone monument and mark that may have been a stake. Reset with 1 1/2" Iron pipe, stones and brick.	3) 12" S.W. Oak NORTH 4.3' 4) 8" S.W. Oak N08E 15.6' 5) 5" S.W. Oak N50E 16.6' 6) 30" W. Oak EAST 43.8' 7) 10" Hickory S87E 31.6' 8) 6" Hickory WEST 5.2' 9) 18" S.W. Oak W'yly 32.8'

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In April of 1994, LSC found a 1" iron pipe using these witnesses:

Fnd. 1 1/2" IP 3.4' N. old E-W fenceline @ S. edge swamp. No brick found. due to high water.	3) 22" Oak N05E 4.28'
	4) 40" Oak N35E 15.64'
	6) 38" Oak S50E 43.81'
	8) 12" Hickory N40W 5.58'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

April 20 1994	R. T. Tietsema	20712	Remon.	Fnd. 1 1/2" Iron Pipe Added a Wash. Co. Remon. Cap.	3) 20" Oak NORTH 4.30' to nail & R.T. 4) 30" Oak N25E 15.64' to nail & R.T. 6) 36" Oak S85E 43.95' to nail & R.T. 8) 10" Hickory S85W 5.57' to nail & R.T.
---------------	----------------	-------	--------	---	---

It is our opinion that this corner represents the original corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by R. Timothy Tietsema Date May 6 1994
Surveyor's Michigan License No. 20712

RECORDED
 WASHTEENAW COUNTY, MI
 DEC 1 11 27 AM '94
 PEGGY M. HAINES
 COUNTY CLERK/REGISTER
 LIBER 1 PAGE 130 RM
 - COPY -
 Register of Deeds Stamp & File Number

CONTINUED FROM A. ON FRONT:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
8/25/1976	N. N. Fahrner JOB NO: 13907	17620	L4P245	Boundary	Fnd. Iron Pipe	3) 18" SW Oak NORTH 4.3' 4) 22" SW Oak N08E 15.6' 5) 8" SW Oak N50E 16.5' 6) 36" W. Oak EAST 16.5' 7) 16" Hickory S87E 31.6' 9) 24" SW Oak W'y 32.8'
10/14/1976	N. N. Fahrner JOB NO: 14451	17620		Boundary	Fnd. 1 1/2" Iron Pipe	3) 18" SW Oak NORTH 4.3' 4) 22" SW Oak N08E 15.6' 5) 8" SW Oak N50E 16.5' 6) 36" W. Oak EAST 43.8'
4/25/1989	N. N. Fahrner JOB NO: 22462	17620		Boundary	Fnd. 1 1/2" Iron Pipe	3) 18" SW Oak NORTH 4.3' 4) 22" SW Oak N08E 15.6' 5) 8" SW Oak N50E 16.5' 6) 36" W. Oak EAST 43.8'
12/21/1989	N. N. Fahrner JOB NO: 22752	17620		Boundary	Fnd. 1 1/2" Iron Pipe	3) 18" SW Oak NORTH 4.3' 4) 22" SW Oak N08E 15.6' 5) 8" SW Oak N50E 16.5' 6) 36" W. Oak EAST 43.8'
April 1989	R. T. Tietsema JOB NO: 22752	20712		Boundary	Fnd. 1 1/2" Iron Pipe	3) 22" Oak N05E 4.28' 4) 40" Oak N35E 15.64' 6) 38" Oak S50E 43.81' 8) 12" Hickory N40W 5.58'

APPROVED
DATE 5/3/94
CO. REP. K

7

