

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

Washtenaw
(County)

Located In:

Corner Code #

Public Land Survey

T 1S R 4E

K11

Property Controlling
in Section
Miscellaneous
Property in Sec.

S T R
S T R
S T R
S T R



5094761
Page: 1 of 1
02/07/2000 02:55P

Register of Deeds Stamp & File Number

Lot No. _____ Recorded Plat _____
Private Claim _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

R. Timothy Tietsema, in a field survey on 20 September, 1999, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

1819	GLO(Wampler)	Fld. Notes	Set Original Corner	Set post corner of Sections 25, 26, 35 & 36 Corner in Lake - 10 chains (660') North of South edge of Lake
03/21/1977	N. Fahrner 17620	Survey Job #14642		Corner inaccessible
01/08/1977	Atwell-Hicks John Litchfield 13352	Survey Job #31921		Corner inaccessible
11/27/1978	N. Fahrner 17620	Survey Job #16497		Corner inaccessible
09/25/1979	Atwell-Hicks John Litchfield 13352	Plat "Hidden Lake Estates" L.22, P. 37-44		Corner shown as monumented

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of monumentation or accessories found in vicinity of corner's location. Location of the corner was established at the intersection of the West line of Section 25 and the South line of Section 26 as shown on the Plat of "Hidden Lake Estates" (L. 22, P. 37-43). The W 1/4 corner of Section 25 and the concrete monument found at the SW corner of Lot 7 of "Hidden Lake Estates" were used for establishing the West line of Section 25. The S 1/4 Corner of Section 26 and the concrete monument at the SW corner of Lot 13 of "Hidden Lake Estates" were used for establishing the South Line of Section 26.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4"x24" iron pipe over 1/2"x60" iron rod with Washtenaw County Remonumentation Cap in marshy area, approximately 25 feet north of North shore of Wylie Lake and approximately 30 feet south of southerly edge of heavy brush, with Michigan State Plane Coordinate values of North 312,500.71 and East 13,244,019.15. Accessories established as follows:

- 1) 3" Tamarack N25E 50.96' Set P.K. nail with remonumentation washer on east side.
- 2) 3" Tamarack N20W 59.26' Set P.K. nail with remonumentation washer on east side.
- 3) Concrete monument N'y 1319.80'
SW Corner Lot 7
Hidden Lake Estates
- 4) Concrete monument W'y 662.35'
SW Corner Lot 13
Hidden Lake Estates

APPROVED
DATE 11/22/99
CO. RE: KA



I find that this corner represents the best available evidence for the position of the original corner. This corner ratified by the Washtenaw County Peer Committee on November 22, 1999.

Signed by R. Timothy Tietsema
Surveyor's Michigan License No. 20712

Date NOV 22 1999