

SURVEY & REMONUMENTATION

MAY - 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Washtenaw

(County)

Located In:

Corner Code ~~##~~

- 1. Public Land Survey T 1S R 4E K-12
 T R _____
 T R _____
 T R _____
- 2. Property Controlling S T R _____
 in Section S T R _____
- 3. Miscellaneous S T R _____
 Property in Sec. S T R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

RECORDED
 WASHTEENAW COUNTY, MICH.
 Dec 1 11 28 AM '94
 PEGGY M. HAINES
 COUNTY CLERK/REGISTRAR
 LIBER
 1 PAGE 136 RM
 Register of Deeds Stamp & File Number

- Copy -

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, R Timothy Tietsema, in a field survey on January 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES	
1819	GLO (Wampler)			Fld. Notes	Set Original Corner Set 1/2 mile post.	1) 40" W. Oak S60W	22 links (14.52')
						2) 10" W. Oak S40E	69 links (45.54')
4/17/1968	N. N. Fahrner JOB NO: 1606	17620		Boundary	Fnd. Iron Pipe	No witnesses given.	
May 1971	Charles C. Wilson	13604	L1P35		Fnd. 1 1/4" Iron Pipe Subsequent survey indicated point used is same point.	3) 20" Oak S85W	61.4'
						4) 40" Oak N7y	2.0'
						5) 12" Oak N85E	21.2'

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In January of 1994, LSC found a 1 1/4" Iron pipe using these witnesses:

Fnd 1 1/4" Iron Pipe in E-W fenceline.	4) 40" Oak 5) 10" Oak 7) 6" Cherry	N7y N85E S85W	2.0' 22.2' 14.0'
---	--	---------------------	------------------------

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

January 1994	R. T. Tietsema	20712	Remon.	Fnd. 1 1/4" Iron Pipe in E-W fenceline & old N-S fenceline.	8) 36" Oak EAST	28.19' to nail & R.T.
					9) 5" Cherry S60E	10.94' to nail & R.T.
					10) 7" Cherry S80W	6.79' to nail & R.T.
					7) 12" Cherry N80W	13.90' to nail & R.T.
					5) 16" Stump EAST	22.2' to center
					11) 10" Dbl. Cherry N75W	31.20' to nail & R.T.
					4) @ South/Southeast base of 56" Oak	

It is our opinion that this corner represents the original corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by R Timothy Tietsema Date October 3, 1994
 Surveyor's Michigan License No. 20712

CONTINUED FROM A. ON FRONT:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
8/25/1976	N. N. Fahmer JOB NO: 13907	17620		Boundary	Fnd. 1" Iron Pipe	5) 10" Oak N85E 22.2' 6) 48" Oak SOUTH 0.1' 7) 6" Cherry S85W 14.0'
10/14/1976	N. N. Fahmer JOB NO: 14451	17620		Boundary	Fnd. 1" Iron Pipe	5) 10" Oak N85E 22.2' 6) 48" Oak SOUTH 0.1' 7) 6" Cherry S85W 14.0'
10/26/1988	N. N. Fahmer JOB NO: 22152	17620		Boundary	Fnd. 1" Iron Pipe	5) 10" Oak N85E 22.2' 6) 48" Oak SOUTH 0.1' 7) 6" Cherry S85W 14.0'

APPROVED
 DATE 7/11/94
 CO. REP. KA

7

