

SURVEY & REMONUMENTATION

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Washtenaw
(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>1S</u> R <u>4E</u> | <u>K-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED
 WASHTENAW COUNTY, MI
 Dec 1 11 28 AM '94
 PEGGY M. HAINES
 COUNTY CLERK/REGISTER
 LIBER 1 PAGE 138 Rm
 Register of Deeds Stamp & File Number

I, R. Timothy Tietsema, in a field survey on January 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- Copy -

	A	B	C	D	E	F	G	H	I	J	K	L	I	
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
1819	GLO (Wampler)			Fld. Notes	Set Original Corner of Sections 35 & 36.	1) 10" B. Oak S75 1/2E 16 links (10.56') 2) 3.16 chains (208.56') East of Corner of Section 1 & 2, T2S, R4E, Lima Twp.
8-3-1936	W. J. Armstrong	W.C.R.C.		Resurvey	Fnd. old wood stake. Reset with 1 1/2" x 36" Iron pipe, stones & brick.	3) 8" B. Oak N87E 16.1' 4) 8" B. Cherry WEST 96.1' 5) 4" B. Cherry N88W 11.2' 6) 4" B. Oak W'y 32.8' 7) 4" B. Oak N50W 8.1'

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In January of 1994, LSC found a 1 1/2" Iron pipe using these witnesses:

Fnd 1 1/2" Iron Pipe	3) 30" B. Oak	S87E	16.30'
	8) R.R. Fnc. Post	S75E	11.90'
	9) R.R. Fnc. Post	W'y	4.60'
	11) Large Stone	N15W	5.0'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

January 1994	R. T. Tietsema	20712	Remon.	Fnd. 1 1/2" Iron Pipe	3) 30" B. Oak S87E 16.28' to nail & R.T.
					8) RR Fnc. Post S75E 11.86' to nail & R.T.
					9) RR Fnc. Post N89W 4.64' to nail & R.T.
					11) Large Stone N15W 5.0'

It is our opinion that this corner represents the original corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by R. Timothy Tietsema Date October 3, 1994
Surveyor's Michigan License No. 20712

1

- copy -

CONTINUED FROM A. ON FRONT:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
8/25/1976	N. N. Fahrner JOB NO: 13907	17620	L4P244		Fnd. Iron Pipe	3) 24" B. Oak N87E 16.1' 4) 8" Stump WEST 96.1' 5) 4" Stump N88W 11.2' 7) 4" Stump N50W 8.1' 8) RR Tie fence post S89E 11.9' 9) RR Tie fence post N89W 4.6'
1/22/1979	N. N. Fahrner JOB NO: 16456	17620		Boundary	Fnd. 1 1/2" Iron Pipe	3) 24" B. Oak N87E 16.1' 4) 8" Stump WEST 96.1' 5) 4" Stump N88W 11.2' 7) 4" Stump N50W 8.1' 8) RR Tie fence post S89E 11.9' 9) RR Tie fence post N89W 4.6'
7/9/1979	N. N. Fahrner JOB NO: 17015	17620		Boundary	Fnd. 1 1/2" Iron Pipe	3) 24" B. Oak N87E 16.1' 4) 8" Stump WEST 96.1' 5) 4" Stump N88W 11.2' 7) 4" Stump N50W 8.1' 8) RR Tie fence post S89E 11.9' 9) RR Tie fence post N89W 4.6'
5/27/1988	N. N. Fahrner JOB NO: 21960	17620		Boundary	Fnd. 1 1/2" Iron Pipe	3) 24" B. Oak N87E 16.1' 4) 8" Twin B. Cherry Stump WEST 96.1' 5) 4" B. Cherry Stump N88W 11.2' 7) 4" B. Oak Stump N50W 8.1'
10/26/1988	N. N. Fahrner JOB NO: 22152	17620		Boundary	Fnd. 1 1/2" Iron Pipe	3) 24" B. Oak N87E 16.1' 4) 8" Stump WEST 5) 4" Stump N88W 11.2' 7) 4" Stump N50W 8.1' 8) RR Tie fence post S89E 11.9' 9) RR Tie fence post N89W 4.6'
4/25/1989	N. N. Fahrner JOB NO: 22462	17620		Boundary	Fnd. 1 1/2" Iron Pipe	3) 24" B. Oak N87E 16.1' 4) 8" Stump WEST 5) 4" Stump N88W 11.2' 7) 4" Stump N50W 8.1' 8) RR Tie fence post S89E 11.9' 9) RR Tie fence post N89W 4.6'
April 1991	R. T. Tietsema JOB NO: 08890	20712		Boundary	Fnd. 1 1/2" Iron Pipe	3) 32" Oak N87E 16.28' 8) Fence Post S89E 11.84' 9) Fence Post N89W 4.64' 10) 34" Oak N88E 102.58'
February 1992	R. T. Tietsema JOB NO: 13092	20712		Boundary	Fnd. 1 1/2" Iron Pipe	3) 30" B. Oak S87E 16.30' 8) RR Fnc. Post S75E 11.90' 9) RR Fnc. Post W'ly 4.60' 11) Large Stone N15W 5.0'

APPROVED

DATE 2/8/99

CO. REP.

7