

SURVEY &
REMONUMENTATION

MAY - 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Washtenaw

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>1S</u> R <u>4E</u> | <u>L-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED
WASHTENAW COUNTY, MI
DEC 1 11 29 AM '94
PEGGY M. HAINES
COUNTY CLERK/REGISTER
-COPY-
LIBER 1 PAGE 142*

Register of Deeds Stamp & File Number

I, R. Timothy Tietsema, in a field survey on April 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

-copy-

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
1819	GLO (Wampler)			Fld. Notes	Set Original Corner	Set 1/4 Section post (Bearings omitted).
8-4-1936	W. J. Armstrong	W.C.R.C.		Resurvey	Fnd. old wood stake. Set iron pipe, stones, and bricks. The North post Sec. 1 Lima stands 106.7' West.	1) 28" B. Cherry S87E 52.0' 2) 24" W. Oak S45W 154.8' 3) 20" W. Oak S60W 119.1' 4) 18" B. Oak S80W 122.3'

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

in April of 1994, LSC found a 1/2" iron rod in a concrete monument using these witnesses:

Fnd. 1/2" IR in Concrete Monument in E-W fence line.	1) 30" B. Cherry	S87E	52.0'
	3) 24" W. Oak	S60W	119.1'
	5) 18" Cherry	N60W	23.71'
	6) 3-6" Tw. Hickory	N70W	18.26'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

April 20 1994	R. T. Tietsema	20712	Remon.	Fnd. 1/2" Iron Rod Added a Wash. Co. Remon. Cap.	1) 36" 1/2 Dead Cherry S75E 52.00' to nail & R.T. 3) 40" Oak S75W 118.76' to nail & R.T. 5) 24" Dbl. Cherry N60W 23.91' to nail & R.T. 6) 9" Tw. Oak N65W 18.28' to nail & R.T. 9) 28" Cherry N70W 112.91' to nail & R.T.
---------------	----------------	-------	--------	--	---

It is our opinion that this corner represents the original corner and is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by R. Timothy Tietsema Date May 9 1994

Surveyor's Michigan License No. 20712

CONTINUED FROM A. ON FRONT:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
3/13/1967	N. N. Fahrner JOB NO: 1229	17620		Boundary	Fnd. Iron Pipe	No witnesses given.
10/16/1967	N. N. Fahrner JOB NO: 1789	17620		Boundary	Fnd. Iron Pipe	No witnesses given.
6/4/1970	N. N. Fahrner JOB NO: 4490	17620		Boundary	Fnd. Iron Pipe	No witnesses given.
5/18/1972	N. N. Fahrner JOB NO: 8496	17620	L2P141	Boundary	Fnd. 1 1/2" Iron Pipe	1) 30" B. Cherry S87E 52.0' 2) 27" W. Oak S45W 154.8' 3) 24" W. Oak S60W 119.1' 4) 20" B. Oak S80W 122.3'
9/6/1978	N. N. Fahrner JOB NO: 16263	17620		Boundary	Fnd. 1 1/2" Iron Pipe	1) 30" B. Cherry S87E 52.0' 2) 27" W. Oak S45W 154.8' 3) 24" W. Oak S60W 119.1' 4) 20" B. Oak S80W 122.3'
1/22/1979	N. N. Fahrner JOB NO: 16456	17620		Boundary	Fnd. 1 1/2" Iron Pipe	1) 30" B. Cherry S87E 52.0' 2) 27" W. Oak S45W 154.8' 3) 24" W. Oak S60W 119.1' 4) 20" B. Oak S80W 122.3'
5/14/1979	N. N. Fahrner JOB NO: 16781	17620		Boundary	Fnd. 1 1/2" Iron Pipe	1) 30" B. Cherry S87E 52.0' 2) 27" W. Oak S45W 154.8' 3) 24" W. Oak S60W 119.1' 4) 20" B. Oak S80W 122.3'
7/9/1979	N. N. Fahrner JOB NO: 17015	17620		Boundary	Fnd. 1 1/2" Iron Pipe	1) 30" B. Cherry S87E 52.0' 2) 27" W. Oak S45W 154.8' 3) 24" W. Oak S60W 119.1' 4) 20" B. Oak S80W 122.3'
5/27/1988	N. N. Fahrner JOB NO: 21960	17620		Boundary	Fnd. 1 1/2" Iron Pipe	1) 30" B. Cherry S87E 52.0' 2) 27" W. Oak S45W 154.8' 3) 24" W. Oak S60W 119.1' 4) 20" B. Oak S80W 122.3'
9/6/1989	C. C. Wilson JOB NO: 21960	13604		Plat of Stoney Field Acres.	Fnd. 1 1/2" Iron Pipe Replaced with a 1/2" Iron Rod in Conc. Monument.	5) 18" Cherry N60W 23.71' 6) 3-6" Tw. Hickory N70W 18.26' 7) 30" Cherry S75E 51.85' 8) 2'x2' Flat Rock N55W 3.05'

APPROVED

DATE 5/3/94

CO. REP. K