

RFI

81-11-1001

2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in

Washtenaw (County)

Located In:

Corner Code #

1. Public Land Survey

T 1S R 4E
T R
T R
T R
S T R
S T R
S T R
S T R

M11
Barcode
Peggy M. Haines - Washtenaw Co. CORREN

Copy

5094764
Page: 1 of 1
02/07/2000 02:55P
L-3 P-42

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claim

I, R. Timothy Tietsema, in a field survey on 15 February, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Cell (11, M) contains a circled '1'.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with columns: Date, Name, Job #, Survey, Fld. Notes, Set Original Corner, and Monument/Accessories. Includes entries for GLO(Wampler), H. H. Atwell, N. Fahrner, John Snyder, and R.G. Macomber.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" iron pipe in N-S fence line and using accessory 1.

APPROVED
DATE 11/22/99
R. TIMOTHY TIETSEMA

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Washtenaw County Remonumentation Cap on existing 3/4" iron pipe in N-S fence line and 99 feet south of fence corner with fence running south and west, with Michigan State Plane Coordinate values of North 311,643.63 and East 13,249,149.10. Accessories perpetuated or established as follows.

- 1) Wood fence corner North 99.18'
5) 8" Poplar S73E 15.38'
6) 12" Elm S54E 38.33'
7) 12" Elm S25E 49.16'
8) 8" Elm NS3W 21.13'
Set P.K. nail with Washtenaw County remonumentation cap on south side.

I find that this corner represents the best available evidence for the position of the original corner. This corner ratified by the Washtenaw County Peer Committee on November 22, 1999.

Signed by [Signature] Date
Surveyor's Michigan License No. 20712

NOV 23 1999

