

**SURVEY &  
REMONUMENTATION**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Washtenaw  
(County)

**COMMISSION**

Located In:

Corner Code #

1. Public Land Survey	T 1S	R 4E	M-13
	T	R	
	T	R	
	T	R	
2. Property Controlling In Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

RECORDED  
WASHTENAW COUNTY, MICH.  
Dec 1 11 29 AM '94  
PEGGY N. HAINES  
COUNTY CLERK/REGISTRAR  
-COPY-  
LIBER 1 PAGE 148 RN  
Register of Deeds Stamp & File Number

I, R. Timothy Tietsema, in a field survey on July 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- COPY -

A	B	C	D	E	F	G	H	J	K	L
2	6	5	4	3	2					
3										
4	7	8	9	10	11					
5										
6	18	17	16	15	14					
7										
8	19	20	21	22	23					
9										
10	30	29	28	27	26					
11										
12	31	32	33	34	35					
13										

**A. Description of original monument and accessories and/or subsequent restoration:**

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
2/28/1819	GLO (Wampler)			Fld. Notes	Set Original Corner	No witnesses.
1930's	H. H. Atwell	W.C.R.C.		Resurvey	Iron Pipe	1) 30" W. Oak N25E 98.0' 2) 12" F. Post N85W 26.4' 3) 12" F. Post SOUTH 2.5'

**CONTINUED ON BACK**

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

In July of 1994, LSC found a 3/4" Iron rod with an Eyelet on top using these witnesses:

Fnd 3/4" Iron Rod w/ eyelet on top in N-S fenceline.	1) 36" W. Oak	N25E	96.95'
	2) F. Post	N85W	26.74'
	3) F. Post	S'y	4.23'
	4) F. Post	S50W	21.20'

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

July 8 1994	R. T. Tietsema	20712	Remon.	Fnd. 3/4" Iron Rod with Eyelet on top. In N-S fenceline.	1) 48" Oak N29E 98.05' to nail & R.T. 2) Wood Fnc Post. SOUTH 4.26' to nail & R.T. 3) Wood Fnc. Post S80W 26.99' to nail & R.T. 4) Wood Fnc. Post S65W 21.12' to nail & R.T. 5) 10" Cherry N05E 52.38' to nail & R.T.
-------------	----------------	-------	--------	--	---

It is our opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

Signed by R. Timothy Tietsema Date October 3, 1994  
Surveyor's Michigan License No. 20712

1

CONTINUED FROM A. ON FRONT:

DATE	SURVEYOR	LS#	LCRC	SURVEY	MONUMENT DESC.	WITNESSES
12/18/1990	Craig A. Eckfeld	33135	L7P264		Fnd. Iron Rod with Eyelet on top.	1) 36" W. Oak N25E 96.95' 2) F. Post N85W 26.74' 3) F. Post S'y 4.23' 4) F. Post S50W 21.20'

201-9

APPROVED  
DATE 7/11/94  
CO. REP. KA

2

