

SECTION

RECORDED  
WASHTENAW COUNTY, MI

JAN 22 8 31 AM '98

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW  
(County)

Located In:

Corner Code #

Webster Twp.  
G-12

- 1. Public Land Survey T 1 S R 5 E
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

PEGGY M. DAINES  
COUNTY CLERK/REGISTER

- COPY -  
- COPY -

Liber 00002 Page 0031 RM

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, JOHN JEKABSON, in a field survey on 14 October, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1819	G.L.O. - T. WAMPLER	SET POST	White Oak, 20" Do, 20"	S 38° W 9Lks N 87° E 29Lks	
1937, 6 Oct.	WASHTENAW CO. ROAD	Found 1/2" Iron Pipe.	5" Hickory	N 61° E 17.6	1
COMMISSION	W.J. ARMSTRONG #2444	Another Iron Pipe 1/4" stands East 13.9 feet.	8" Elm	S 30° E 28.3	2
			12" Hickory	S 76° W 32.5	3
			5" Hickory	N 82° W 36.8	4
			5" Hickory	N 80° W 36.0	5
			15" W. Oak	N 62° W 60.7	6
			8" W. Oak	N 31° W 25.9	7
			Iron Pipe 1/4"	East 13.9	8

SEE BACK OF THIS SHEET (NEXT PAGE)  
FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1"X24" IRON PIPE 8" BELOW GRAVEL ROAD SURFACE. WITNESSED AND REMOVED AND RECEIVED NO READING FROM ANOTHER IRON. RESET 1"X24" ORIGINAL IRON PIPE WITH REMON. CAP 6" BELOW GRAVEL ROAD SURFACE.

USING 3 WITNESSES FROM SECTION "A"



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

RESET 1"X24" ORIGINAL IRON PIPE WITH REMON. CAP 6" BELOW GRAVEL ROAD SURFACE..	PK & RT in S sd 13" Shag. Hickory	N 82° W 44.95	11"
	PK & RT in S sd 8" Shag. Hickory	N 80° W 35.77	12"
	PK & RT in S sd 18" Shag. Hickory	N 75° W 19.40	9"
	PK & RT in W sd 10" Elm	S 20° E 79.37	13"
	Center of Stump	S 76° W 32.6	3"

APPROVED  
DATE 11/10/97  
CO. REP. Kx

Legend:  
PK & RT = PK Nail & Washtenaw Co. Remon. Tag  
\* Indicates Previously Used

I conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by [Signature] Date 4 December, 1997  
Surveyor's Michigan License No. 19836

- COPY -

Liber 00002 Page 0032 RM

Continuation of Section "A"

1997 WASHTENAW COUNTY REMONUMENTATION PROGRAM  
 WEBSTER TOWNSHIP TOWN 1 SOUTH, RANGE 5 EAST  
 G-11 (SECTION CORNER COMMON TO SECTIONS 27, 28, 33, & 34)

History compiled by: I. John Jekabson P.S. # 19836  
 Roskelly, Jekabson & Assoc. P.C.

DATE	COMPANY SURVEYOR & P.S. #	JOB #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1964	ATWELL-HICKS, INC.	23014			Found Iron Pipe	No Witnesses			
21 December 1973	ATWELL-HICKS, INC.	28234		N.W. 1/4 Sec. 34	Found 1/2" I.P.	22" Shag. Hickory 20" Hickory	N 33° E 35.4 S 40° W 53.1	2* 3*	
21 February 1989	JOHN L. SNYDER # 13552 Field Book					18" Shag. Hickory 18" Hickory	S 63 1/2° W 54.9 S 45° E 21.5	4* 5	
July 1989	LAND SURVEYING CONSULTANTS R. TIMOTHY TIETSEMA # 20712	053897-155E28		S. 1/4 Sec. 28	Frnd. 1/2" IP	30" Hickory 36" Oak 30" Oak 26" Hickory	N 35° E 35.39 S 55° E 21.61 S 85° E 65.89 S 45° W 53.00	2* 6 7 3*	
November 1996	LAND SURVEYING CONSULTANTS R. TIMOTHY TIETSEMA # 20712	13196-155E33		N.E. 1/4 Sec. 33	Frnd. 1/2" IP	Same as July, 1989			
5 April 1996	ATWELL-HICKS, INC. TODD D. SHELLY # 41111	42346		S.W. 1/4 Sec. 27	Found 1/2" Iron Pipe	Nail E face 8" Elm Nail NW face 16" Oak Nail SW face 24" Oak Nail NW face 20" Hickory	N 30° W 47.63 S 45° W 52.94 S 42° E 21.57 N 38° E 35.42	8 3* 6* 2*	

Legend:  
 \* Indicates Previously Used