

MAR 09 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 22 8 31 AM '98

SECTION

For corners in

PEGGY M. HAINES
COUNTY CLERK/REGISTER

WASHTENAW
(County)

Located In:

Corner Code #

Webster Twp.

1. Public Land Survey	T 1 S	R 5 E	G - 13
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

- COPY -

- COPY -

Liber 00002 Page 0033 RM
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JOHN JEKABSON, in a field survey on 14 October, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1819 G.L.O. - T. WAMPLER	SET POST	Hickory, 12"	N 35° E	20Lks.	
		White Oak, 34"	N 50° W	41Lks.	
1933, 21 Aug. WASHTENAW CO. ROAD COMMISSION W.J. ARMSTRONG #2444	Found a 1" Iron Pipe with a pile of stones and bricks around it. Did not reset.	27" Hickory	N 60° E	60.7	1
		36" Elm	S 63° E	57.1	2
		18" Elm	S 37½° E	34.05	3
		14" Walnut	S 46½° W	42.35	4
		10" Walnut	S 74½° W	94.4	5

SEE BACK OF THIS SHEET (NEXT PAGE)
FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND ¾" CAPPED IRON PIPE
AT ASPHALT ROAD SURFACE
USING 5 WITNESSES FROM SECTION "A"



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET MON. BOX AND IRON PIPE WITH REMON CAP	Center of Dead 27" Shag. Hickory	N 60° E	60.7	1"
	PK & RT in NE sd 12" Cherry	S 47° E	51.66	6"
	Center of Old Stump	S 38° E	34.05	3"
	PK & RT in SE sd 24" Black Walnut	S 47° W	42.35	4"
	PK & RT in SE sd Utility Pole	S 60° W	50.08	9"
	PK & RT in S sd 20" Black Walnut	S 75° W	94.40	5"

APPROVED
DATE 11/10/97
CO. REP. MA

Legend:
PK & RT = PK Nail & Washtenaw Co. Remon. Tag
* Indicates Previously Used

I conclude that after careful study of the record documentation and field observations, that this corner is a careful and faithful perpetuation of the position of the original corner.

Signed by I. John Jekabson
Surveyor's Michigan License No. 19836

Date 4 December, 1997

- Copy -

Liber 000002 Page 0034 RM

Continuation of Section 'A'

1997 WASHTENAW COUNTY REMONUMENTATION PROGRAM
WEBSTER TOWNSHIP TOWN 1 SOUTH, RANGE 5 EAST
G-12 (1/4 CORNER COMMON TO SECTIONS 33 & 34)

History compiled by: I. John Jekabson P.S. # 19896
Roskelly, Jekabson & Assoc. P.C.

DATE	COMPANY SURVEYOR & P.S. #	JOB #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1973 19 March	ATWELL-HICKS, INC. JOHN L. SNYDER # 13352	28237		N.W. 1/4 Sec. 34	Found 1" Iron Pipe	12" Hickory 10" Shag. Hickory 8" Shag. Hickory 20" Hickory Stump	N 75° W 19.4 N 85° W 45.2 N 83° W 44.8 S 76° W 32.6	9 10 11 3*	

Legend:
* Indicates Previously Used