

**SURVEY &  
REMONUMENTATION**

MAY - 1 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WASHTENAW</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>1 S</u> R <u>5 E</u>	<u>1-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED  
 WASHTENAW COUNTY, MI  
 Dec 1 11 38 AM '94  
 PEGGY M. HAINES  
 COUNTY CLERK/REGISTER  
 -COPY-

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, I. JOHN JEKABSON, in a field survey on 20 DECEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1819	G.L.O.	Set Stake	16" W. Oak	S 81° E	60							
1929	13 June	NEIL R. SUTTON	"LOCH ALPINE" PLAT	Set conc. mon.	No Witnesses							
			Liber 8, Pages 26, 27, 28									
1989	13 Mar.	WASHTENAW ENG. CO.	Job # 22366		No Witnesses							
		T.L. SUTHERLAND #24620	Reference to "Loch Alpine" Plat									
1992	3 Feb.	H. LAWRENCE O'DONNELL #28419	P.A. 74 L.C.R.C.	L. 7, P. 304	Found Conc. & Steel Monument with "LA" stamp	12" Elm to nail	N 80° E	23.05	a			
						12" Oak to nail	N 50° W	76.31	b			
						14" Elm to nail	S 45° E	57.28	c			
						12" Pine	N 80° W	128.07	d			

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONC. & STEEL MONUMENT WITH "LA" STAMP, AS PER "LOCH ALPINE" SUB.

ALSO FOUND N.E. COR. SEC. 3, T.2S., R.5E., "LA" MON. MON. TO MON. REC.=376.20 MEAS.=375.08

ALSO USING 4 OF THE ABOVE WITNESSES

RECORDED  
WASHTENAW COUNTY, MI

Dec 1 11 33 AM '94

PEGGY M. HAINES  
COUNTY CLERK/REGISTER  
-COPY-

APPROVED

DATE 2/22/94

CO. REP. H

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND CONC. & STEEL MONUMENT WITH "LA" STAMP	9" Pine (PK N sd.)	N 80° W	128.0	d
	9" Oak (PK & RT NE sd.)	N 50° W	76.31	b
	14" Elm (PK & RT N sd.)	N 80° E	23.05	a
	15" Elm (PK & RT SW sd.)	S 40° E	57.28	c
	Fd. Conc. Mon. w/ "LA" stamp	East	375.08	e

I conclude that after careful study of the record documentation and field observations, that this corner is a careful and faithful perpetuation of the position of the original corner.

Signed by I. John Jekabson

Date 11 October, 1994

Surveyor's Michigan License No. 19836

