

**SURVEY &
REMONUMENTATION**

MAY - 1 1995

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW
(County)

Located In:

Corner Code ##

- | | | | |
|------------------------------------|--------------|--------------|---------------|
| 1. Public Land Survey | T <u>1</u> S | R <u>5</u> E | <u>K - 12</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED
 WASHTENAW COUNTY, MI
 DEC 1 11 35 AM '94
 PEGGY M. HAINES
 COUNTY CLERK/REGISTRAR
 LIBER 1 PAGE 179 Rm
 - Copy -
 Register of Deeds Stamp & File Number

I, I. JOHN JEKABSON, in a field survey on 16 DECEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1819	G.L.O.	Set post	B.O. B	N 18 E	6	
	WAMPLER		W.O. 23	N 72 W	220	
Date Unknown	INFORMATION AT	IRON PIPE		S.E. Cor. School	N 34° W 94.0	A
WASHTENAW ROAD COMMISSION				Burr Oak, 36"	S 9½° W 203.0	B
H.H. ATWELL				S.W. Cor. School	N 47½° W 116.1	C
				Burr Oak, 5"	S 36½° W 49.5	D

SEE BACK OF THIS SHEET (NEXT PAGE) FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON PIPE WITH BRICKS & STONES 6" BELOW GRAVEL SURFACE USING 3 WITNESSES FROM SECTION "A"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Alum. Remon. Cap on 1" Iron Pipe	PK & RT NE sd. 26" Burr Oak	N 55° W	138.60	G
	PK & RT E sd. 24" Red Oak	N 10° W	177.46	F
	PK & RT W sd. New D.E. Pole	N 10° E	158.90	J
	PK & RT SE sd. 38" Burr Oak	S 35° W	49.20	D

I conclude that after careful study of the record documentation and field observations, that this corner is a careful and faithful perpetuation of the position of the original corner.



Signed by I. John Jekabson Date 6 October, 1994
 Surveyor's Michigan License No. 19836

