

SURVEY & REMONUMENTATION

MAY - 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WASHTENAW</u> <small>(County)</small>	Located In:	Corner Code #:	
1. Public Land Survey	T <u>1 S</u> R <u>5 E</u>	<u>K - 13</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, I. JOHN JEKABSON, in a field survey on 16 DECEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1819 G.L.O. Set stake

1934 17 Jan. WASHTENAW COUNTY ROAD COMMISSION W.J. ARMSTRONG #2444	Found 3" Tile with Stones and Bricks around it. Did not reset	Basswood, 26" Thornapple, 4" Hickory, 12"	N'y by E: 17.55 A N 75° W 29.15 B N 40° E 87.5 C
---	--	---	--

SEE BACK OF THIS SHEET (NEXT PAGE) FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found broken Tile, broken Bricks, and stones.
DID NOT FIND IRON PIPE. Set 1" x 24" Iron Pipe with Alum. Remon. Cap Using N.N. Fahrner's witnesses, 1981 4 June.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x 24" Iron Pipe with Alum. Remon. Cap	C/L 36" Dead Basswood	N 7° E 17.55	A
	C/L 3" Thornapple	N 30° E 36.8	D
	PK & RT SE sd. 20" Hickory	N 30° E 93.35	K
	C/L 4" Thornapple	N 65° E 52.1	E
	PK & RT S sd. 24" Burr Oak	N 75° E 120.33	H
	PK & RT S sd. 13" Elm	S 85° E 43.5	G ?
	PK & RT SW sd. Tw. 6" Hickory	S 45° E 10.47	F ?

I conclude that after careful study of the record documentation and field observations, that this corner is a careful and faithful perpetuation of the position of the original corner

Signed by *I. John Jekabson* Date 6 October, 1994
Surveyor's Michigan License No. 19836

RECORDED
 WASHTENAW COUNTY, MI
 Dec 1 11 35 AM '94
 PEGGY N. HAINES
 COUNTY CLERK/REGISTER
 LIBER 1 PAGE 181 RM
 Register of Deeds Stamp & File Number

- copy -

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



1

