

REMONUMENTATION

MAY - 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 1 S R 5 E L - 9
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED
WASHTENAW COUNTY, MI
DEC 1 11 36 AM '94
PEGGY H. HAINES
COUNTY CLERK/REGISTER
-copy-

Register of Deeds Stamp & File Number

I, I. JOHN JEKABSON, in a field survey on 26 OCTOBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1819 G.L.O. Set post W.O. 18 N 85 E 16
Do 29 S 4 E 34

1934 17 Jan. WASHTENAW CO. Set Iron Pipe, stones, and bricks Burr Oak, 10" N 68° E 60.1 A
ROAD COMMISSION Burr Oak, 6" S 73° E 112.0 B
W.J. ARMSTRONG Burr Oak, 6" S 45° E 53.4 C
Burr Oak, 10" S 31° E 40.7 D
Burr Oak, 6" S 55° W 44.0 E
Burr Oak, 4" N 23° W 31.2 F

SEE BACK OF THIS SHEET (NEXT PAGE) FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND VERY DETERIORATED 1" X 36" IRON PIPE WITH BRICKS AND STONES.
USING 4 WITNESSES FROM SECTION "A"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replace old 1" x 36" Iron Pipe with new 1" Iron Pipe and Alum. Remon Cap.	4" Dia. x 4" High St. Fence Post	West	21.60	S
	PK & RT NE sd. 18" Red Maple	N 60° W	22.63	P
	PK & RT W sd. 11" Shag. Hickory	N 10° W	15.48	Q
	PK & RT NW sd. 26" Red Oak	N 50° E	50.15	T
	PK & RT S sd. 16" Hickory	N 75° E	36.21	U
	PK & RT S sd. 12" White Oak	S 75° E	4.55	N
	PK & RT E sd. 16" Cherry	S 10° E	34.75	O

I conclude that after careful study of the record documentation and field observations, that this corner is a careful and faithful perpetuation of the position of the original corner.



Signed by I. John Jekabson Date 6 October, 1994
Surveyor's Michigan License No. 19836

1993 WASHTENAW COUNTY REMONUMENTATION PROGRAM

WEBSTER TOWNSHIP TOWN 1 SOUTH, RANGE 5 EAST
L-9 (1/4 CORNER COMMON TO SECTION 24 & SECTION 25)

History compiled by:
I. John Jekabson P.S. # 19836
Roskelly, Jekabson & Assoc. P.C.

DATE	COMPANY SURVEYOR JOB #	P.S. #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	WITNESS ID	COMMENT
Unknown	INFORMATION AT WASHTENAW COUNTY ROAD COMMISSION					4" Oak 4" Hick. 15" Oak 4" W. Oak 10" Elm 3" W. Oak 4" W. Oak	G H I J K L M	
1977 31 Oct.	ROSKELLY, JEKABSON & ASSOC., P.C. ROBERT P. ROSKELLY Job # 77-10-60	#18663		N.E. 1/4 SEC. 25	Found 1 1/2" Iron Pipe	Nail 12" White Oak Nail 12" Cherry Nail 15" Red Maple Nail 10" Hickory	N O P Q	
1980 27 Oct.	ROBERT P. ROSKELLY	#18663	Liber 6, Page 45		Found 1 1/2" Iron Pipe	Same as 1977, 31 Oct.		
1982 27 July	WASHTENAW ENG. CO. NORMAN N. FAHRNER Job # 18304	#17620		W. 1/2 SEC. 24	Found 1/2" Iron Pipe	10" Hickory to nail 12" Wild Cherry to nail 16" Hickory to nail	Q O P?	
1985 22 July	AYRES, LEWIS, NORRIS & MAY, INC. CHARLES C. WILSON	#13604		East 1/2 SEC. 24	Found 1 1/2" Iron Pipe	Nail 12" W. Oak to nail Nail 12" Cherry to nail Nail 15" R. Maple to nail Nail 10" Hickory to nail	N O P Q	
1986 18 Sept.	ATWELL-HICKS, INC. ROBERT G. MACOMBER Job # 36612	#27453		East 1/2 SEC. 24	Found 1" C.I.P.	Nail S/S 14" Oak Nail W/S 12" Hickory Nail S/S 11" Oak	N Q R	
1989 24 June	ATWELL-HICKS, INC. ROBERT G. MACOMBER Job # 38421	#27453		East 1/2 SEC. 24	Found 1" Iron Pipe	Same as 1986, 18 Sept.		

2

APPROVED
DATE 2/22/94
CO. REP. *[Signature]*