

MAY 10 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW (County)

Located In:

Corner Code #

Northfield Twp. E-12

- 1. Public Land Survey T1S R 6E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R



5094740 Page: 1 of 1 02/07/2000 02:55P

Peggy M. Haines - Washtenaw Co. CORREM L-3 P-3

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, JOHN JEKABSON, in a field survey on 22 July, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Cell 12,33 contains a black dot.

A. Description of original monument and accessories and/or subsequent restoration:

1819 G.L.O. - T. Wampler SET POST Deputy Surveyor

1941, 8 Aug. WASHTENAW CO. ROAD COMMISSION W.J. ARMSTRONG #2444 Found an old wood stake, stones. Set 1"x26" Iron Pipe and stones.

Table listing monument types and distances: Black Cherry 14" North 3.6 1, Black Cherry 8" North 5.5 2, Black Ash 24" N 75°E 38.2 3, Elm 5" S 35°E 4.6 4, Twin Elms 3" N 88°W 10.6 5, Black Oak 15" Nly 22.6 6

1963, Sept. DETROIT EDISON COMPANY LARK CORRIDOR Iron - No Witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO TRACE OF IRON PIPE AND WITNESSES SET BY W.J. ARMSTRONG DUE TO REMOVAL OF THE TREES ON THE 1/4 LINE AND GRADING IN THE AREA. SET 1"x24" IRON PIPE USING OTHER IRON PIPES AS PER DETROIT EDISON RIGHT OF WAY DRAWINGS OF LARK CORRIDOR.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table listing monument locations and distances: SE Corner of Detroit Edison Tower N 87°W 429.42 7, SE Corner of Detroit Edison Tower N 76°W 441.25 8, SW Corner of Detroit Edison Tower N 71°E 440.89 9, SW Corner of Detroit Edison Tower N 83°E 427.60 10, Found 1" Iron Pipe North 235.00 11, Found 1" Iron Pipe West 648.10 12

Legend: Mag & RT = Magnetized Nail & Washtenaw Co. Remon. Tag * Indicates Previously Used

I conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner

Signed by [Signature] Date 22 November, 1999 Surveyor's Michigan License No. 19836

APPROVED DATE 9/13/99 CO REP. Kx