

MAY 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW (County)

Located In:

Corner Code #

Northfield Twp. F-11

- 1. Public Land Survey T1 S R 6 E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R



5094743 Page: 1 of 2 02/07/2000 02: L-3 P-8

Peggy M. Haines - Washtenaw Co. CORREM

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-K and rows 2-13. A dot is marked at row 11, column G.

I, JOHN JEKABSON, in a field survey on 12 July, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with 4 columns: Description, Monument, Distance, and Bearing. Includes entries for T. Wampler, WASHTENAW RD., and WASHTENAW CO. ROAD.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1"X24" IRON BAR NEXT TO A 1 1/2"X32" BENT IRON PIPE WITH STONES & BRICKS AROUND THEM. TWO VERY LARGE STONES WERE FOUND, ONE EAST & ONE WEST OF PIPE. REMOVED THE PIPE & BAR. RESET WITH A 1"X24" IRON PIPE W/ REMON CAP, 6" BELOW GRAVEL SURFACE OF NORTHFIELD-CHURCH ROAD. REPLACED ORIGINAL BRICK & STONE.

USING 4 WITNESSES FROM SECTION "A"



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table with 4 columns: Description, Monument, Distance, and Bearing. Includes entries for 1"X24" IRON PIPE, White Oak, Shag Hickory, Burr Oak, and Shag Hickory.

Legend: Mag & RT = Magnetized Nail, Washtenaw Co. Remon. T: * Indicates Previously Used

I conclude that after careful study of the record documentation and field observations, that this corner is a careful and faithful perpetuation of the position of the original corner.

Signed by [Signature] Date 22 November, 1999
Surveyor's Michigan License No. 19836

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS
APPROVED DATE 9/13/99 CO. REP. KA

CONTINUATION OF SECTION 'A'


1999 WASHTENAW COUNTY REMONUMENTATION PROGRAM
 NORTHFIELD TOWNSHIP TOWN 1 SOUTH, RANGE 6 EAST
 F-11 (1/4 CORNER COMMON TO SECTIONS 28 & 33)

History compiled by:
 I. John Jekabson P.S. # 19836
 Jekabson & Associates, P.C.

DATE	COMPANY SURVEYOR & P.S. #	JOB #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1960, 13 April 1963, Sept.	ATWELL-HICKS, INC. DETROIT EDISON COMPANY LARK CORRIDOR	7903 6MS 894-15		NE 1/4 Sec 33 Sections 32, 33, 34, 35, & 36	Found Iron Pipe Iron	No Witnesses No Witnesses			
1970, 16 Feb. 1991, 12 Mar.	ATWELL-HICKS, INC. ROSKELLY, JEKABSON & ASSOC., P.C. I. JOHN JEKABSON # 19836	30202	Liber 7, Page 266	Section 28	No Indication Found Bent 1 1/2" Iron Pipe. Replaced with 1" Iron Bar	No Witnesses Nail 24" Shag. Hickory Nail 18" Red Oak Nail Tr 14" Burr Oak Nail 12" Shag Hickory Nail 8" White Oak Same as above (Liber 7, Page 266)	N 10°E 33.20 S 30°E 36.59 South 50.75 S 60°W 73.55 N 25°W 30.65	1" 6 7 8 9	Found Bent 1 1/2" Iron Pipe. Replaced with 1" Iron Bar
1991, 12 Feb.	ROSKELLY, JEKABSON & ASSOC., P.C. I. JOHN JEKABSON # 19836	91-1-30		Sec 28	Same as above	Same as above (Liber 7, Page 266)			
1991, 20 June	ROSKELLY, JEKABSON & ASSOC., P.C. I. JOHN JEKABSON # 19836	91-2-55		N 1/2 Sec 28	Same as above	Same as above (Liber 7, Page 266)			

* Indicates Previously Used

- Coen -



5094743
 Page: 2 of 2
 02/07/2000 02:55P
 Peggy M. Haines - Washtenaw Co. CORREM L-3 P-9

REF. 02/07/2000
 SECTION