

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

WASHTENAW (County)

Located In:

Corner Code #

Northfield Twp. G-10

Copy

- 1. Public Land Survey T1 S R 6 E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R



Page: 1 of 2
02/07/2000 02:55F
L-3 P-14

Peggy M. Haines - Washtenaw Co. CORREM

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, JOHN JEKABSON, in a field survey on 14 July, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


1819 G.L.O. - T. Wampler SET POST Elm, 14" N 2 1/2° E 2.66 Chs.
Deputy Surveyor

1970, 16 Feb. ATWELL-HICKS, INC. This Corner is halfway and on a straight line between G-9 & G-11. (As shown on Survey) No Monument description & No Witnesses

SEE BACK OF THIS SHEET (NEXT PAGE) FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1"X36" IRON PIPE 6" ABOVE THE GROUND WITH STONES SURROUNDING IT. PULLED THE PIPE, RECEIVED NO FURTHER READING. THE TOP OF THIS PIPE WAS SLIGHTLY BENT AND MUSHROOMED. REPLACED WITH A 1 1/2"X36" GALVANIZED IRON PIPE. SET A REMON CAP 6" ABOVE SURFACE. USING 5 WITNESSES FROM SECTION "A" FOUND THIS CORNER CLOSE TO HALFWAY AND ON A STRAIGHT LINE BETWEEN G-9 & G-11. (TO G-9 = 2637.68 & TO G-11 = 2636.28).



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table with 5 columns: Monument Description, Direction, Distance, Angle, and Witness/Notes. Includes entries for Silver Maple, Cherry, Ash, and Dead Elm.

Legend: Mag & RT = Magnetized Nail & Washtenaw Co. Remon. Tag * Indicates Previously Used

I conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by [Signature] Date 22 November, 1999
Surveyor's Michigan License No. 19836

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, REVISED REVIS

APPROVED DATE 9/13/99 CO. REP. KA

CONTINUATION OF SECTION "A"


1999 WASHTENAW COUNTY REMONUMENTATION PROGRAM
NORTHFIELD TOWNSHIP TOWN 1 SOUTH, RANGE 6 EAST
G-10 (1/4 CORNER COMMON TO SECTIONS 27 & 28)

History compiled by:
I. John Jekabson P.S. # 19836
Jekabson & Associates, P.C.

DATE	COMPANY SURVEYOR & P.S. #	JOB. #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1975 13 Nov.	ATWELL-HICKS, INC. ROBERT J. JAGOW #6998		Liber 4, P. 69		Found Boat Spike in Center of Bit. Pavement	22" Oak 26" Tw. Cottonwood 26" Oak E. end 2" C.M.P. W. end 2" C.M.P.	58.8 99.8 40.5 27.9 28.9		This can not be G-10 There is no road or pavement in area.
1991, 12 Mar.	ROSKELLY, JEKABSON & ASSOC., P.C. I. JOHN JEKABSON # 19836		Liber 7, Page 267		Found 1" Iron Pipe	Nail 15" Ash Nail 18" Elm Nail Tri 18" Maple Nail 14" Cherry Nail 18" Ash	3.36 49.98 43.54 25.46 6.17	1 2 3 4 5	
1991, 12 Feb.	ROSKELLY, JEKABSON & ASSOC., P.C. I. JOHN JEKABSON # 19836	91-1-30		Sec 28	Same as above	Same as above (Liber 7, Page 267)			
1991, 20 June	ROSKELLY, JEKABSON & ASSOC., P.C. I. JOHN JEKABSON # 19836	91-2-55		N 1/4 Sec 28	Same as above	Same as above (Liber 7, Page 267)			

* Indicates Previously Used

Copy -



5094746
Page: 2 of 2
02/07/2000 02:55P
Peggy M. Haines - Washtenaw Co. CORREM L-3 P-15

RFM

2000

SECTION