

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW (County)

Located In:

Corner Code ##

Northfield Twp.

- 1. Public Land Survey T 1 S R 6 E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R



5094748 Page: 1 of 2 02/07/2000 02:55P L-3 P-18

Peggy M. Haines - Washtenaw Co. CORREM

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-K and rows 2-13. A circle is drawn at the intersection of column G and row 12.

I, JOHN JEKABSON, in a field survey on 21 July, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with 4 columns: Date/Description, Monument Type, Material, and Dimensions. Includes entries for 1819 G.L.O. - T. Wampler and 1941, 7 Aug. WASHTENAW CO. ROAD COMMISSION W.J. ARMSTRONG #2444.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1"x36" IRON PIPE 6" ABOVE THE GROUND WITH BRICKS AND STONES SURROUNDING IT. THE TOP WAS MUSHROOMED TOO MUCH TO CAP. REPLACED WITH A 1 1/4"x36" GALVANIZED IRON PIPE. SET A REMON CAP 6" ABOVE SURFACE. BRICKS & STONE REMAIN. USING 2 WITNESSES FROM SECTION "A"



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table with 4 columns: Monument Description, Material, Dimensions, and Distance. Includes entry for SET A 1 1/4"x36" GALVANIZED IRON PIPE WITH REMON CAP 6" ABOVE SURFACE.

Legend: Mag & RT = Magnetized Nail & Washtenaw Co. Remon. Tag * Indicates Previously Used

I conclude that after careful study of the record documentation and field observations, that this corner is a careful and faithful perpetuation of the position of the original corner.

Signed by [Signature] Date 22 November, 1999
Surveyor's Michigan License No. 19836

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS REVISED

APPROVED DATE 9/13/99 CO. REP. KA

CONTINUATION OF SECTION "A"


1999 WASHTENAW COUNTY REMONUMENTATION PROGRAM
 NORTHFIELD TOWNSHIP TOWN 1 SOUTH, RANGE 6 EAST
 G-12 (1/4 CORNER COMMON TO SECTIONS 33 & 34)

History compiled by:
 I. John Jekabson P.S. # 19836
 Jekabson & Associates, P.C.

DATE	COMPANY SURVEYOR & P.S. #	JOB. #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1963, Sept.	DETROIT EDISON COMPANY LARK CORRIDOR	8MS 894-15		Sections 32, 33, 34, 35, & 36	Iron	No Witnesses			
1984, 5 May	ROSKELLY, JEKABSON & ASSOC., P.C. I. JOHN JEKABSON # 19836	84-4-67		NW 1/4 Sec 34	Found 1" Iron Pipe	SW corner D.E. Tower SW corner D.E. Tower Nail in 14" White Oak Nail in 16" Red Oak	N 35°E 152.30 N 70°E 122.80 South 55.55 S 20°E 18.05	9 10 11 12	
1985, 19 Feb.	ROSKELLY, JEKABSON & ASSOC., P.C. I. JOHN JEKABSON # 19836		Liber 7, Page 86		Found 1" Iron Pipe	Same as 1984, 4 May (R&U)			
1996, 21 Aug.	LAND SURVEYING CONSULTANTS R. TIMOTHY TIETSEMA # 20712	07796- 156E33		SE 1/4 Sec.33	Found 1" Iron Pipe	SW corner D.E. Tower SW corner D.E. Tower 14" Oak 16" Oak	N 35°E 152.30 N 70°E 122.80 South 55.55 S 20°E 18.05	9* 10* 11* 12*	

* Indicates Previously Used

Copy -



5094748
 Page: 2 of 2
 02/07/2000 02:55P
 L-3 P-19
 Peggy M. Haines - Washtenaw Co. CORREM

REF
 SECTION