

APPROVED

DATE 10-28-96

CO. REP. KJ

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WASHTENAW  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 1 S   R 6 E      L-11  
    T        R        \_\_\_\_\_  
    T        R        \_\_\_\_\_  
    T        R        \_\_\_\_\_
- 2. Property Controlling    S        T        R        \_\_\_\_\_  
    in Section                S        T        R        \_\_\_\_\_
- 3. Miscellaneous            S        T        R        \_\_\_\_\_  
    Property in Sec.         S        T        R        \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

RECORDED  
 WASHTENAW COUNTY MI  
 FEB 18 9 22 AM '97  
 PEGGY R. HAINES  
 COUNTY CLERK/REGISTRAR

Liber 000001 Page 0669

Register of Deeds Stamp & File Number

I, I. JOHN JEKABSON, in a field survey on 23 September, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1819 G.L.O. - T. WAMPLER SET POST

1892 18 June C.S. WOODARD FOUND RENEWED NEW OAK STAKE WITH STONES & BRICKS      B. Cherry, 12" S-W 3.11ch.      1

SEE BACK OF THIS SHEET (NEXT PAGE) FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON BAR AT ASPHALT ROAD SURFACE.  
 REMOVED THE IRON BAR AND DUG 8" BELOW SURFACE.  
 FOUND NO EVIDENCE OF ANOTHER STAKE OR MARKER

USING 3 WITNESSES FROM SECTION "A"

SURVEY &  
REMONUMENTATION

MAY 05 1997

COMMISSION

COPY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1" X 24" IRON PIPE WITH REMON. CAP IN MON BOX	PK & RT in S sd Utility Pole	N 80° W	183.92	13
	S.E. Corner of Garage	N 60° W	172.17	14
	N.E. Corner of Garage	N 55° W	182.30	7*
	PK & RT in NW sd 10" Elm	N 25° E	65.90	10*
	PK & RT in NW sd Utility Pole	S 65° W	67.66	9*



I conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by I. John Jekabson  
 Surveyor's Michigan License No. 19836

Date 11 NOVEMBER, 1996

1986 WASHTENAW COUNTY REMONUMENTATION PROGRAM  
 NORTHFIELD TOWNSHIP TOWN 1 SOUTH, RANGE 6 EAST  
 I-11 (SECTION CORNER COMMON TO SECTIONS 26, 27, 34, & 35)

History compiled by:  
 I. John Jekabson P.S. # 19835  
 Roskelly, Jekabson & Assoc. P.C.

DATE	COMPANY SURVEYOR & P.S. #	JOB. #	LOCATION OF SURVEY MONUMENT	DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
Unknown	WASHTENAW CO. ROAD COMMISSION Hand written in Grid Book				Nail G.T. Pole Nail 20" Elm Nail 6" Elm Nail 18" Elm Nail 20" Elm	N.W. 68.40 S 37° W 54.8 S 26° E 49.0 S 67° E 68.7 S 37° W 54.8	2 3 4 5	
Unknown	ATWELL-HICKS, INC. Old Section Map				6" Elm 18" Elm 36" Elm	S 26° E 49.0 S 67° E 68.7 N 11 1/4° E 125.1	3* 4* 5*	
1975 29 Sept.	ASSOCIATED ENGRS. & SURVEYORS, INC. GLENN RICHARD # 13040	760813	NW 1/4 Section 35	1/4" Iron Rod	N.E. corner Gar. Sign Post Nail in Tel. Pole Same as 1976, 29 Sept.	N 55° W 182.30 N 85° E 61.85 S 65° W 67.45	6 7 8 9	
1976 14 October	ASSOCIATED ENGRS. & SURVEYORS, INC. GLENN RICHARD # 13040		Liber 4 Page 157	Found 3/4" Iron Rod in pavement				
1988 10 May	WASHTENAW ENG CO. NORMAN N. FAHRNER #17620	21812	SW 1/4 Section 26	Found 1/2" Iron Rod	Nail in 6" Elm Nail in 8" Elm Nail in Power Pole	N 30° E 66.06 N 45° E 46.64 S 75° W 67.48	10 11 9*	
1988 21 Sept.	KOSTECKE & ASSOC. INC. RAYMOND J. KOSTECKE #12584	88-6000	SW 1/4 Section 26 & SE 1/4 Sec 27	Fd. Pipe	Spike W. side 6" Elm P.K. S. side 16" Elder	N.E. 48.67 N.E. 86.61	11* 12	
1988 18 Feb.	KOSTECKE & ASSOC. INC. RAYMOND J. KOSTECKE #12584	92-6605	SE 1/4 Section 27	Fd. Pipe	Spike N.W. side Util. Pole Same as 1988, 21 Sept.	S.W. 67.55	9*	

\* INDICATES PREVIOUSLY USED