

APPROVED
 DATE: 10-28-96
 CO. REP: Kg

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 WASHTEENAW COUNTY, MI
 FEB 18 9 22 AM '97
 PERRY M. HAINES
 COUNTY CLERK/REGISTER

For corners in

<u>WASHTEENAW</u> <small>(County)</small>	Located In:	Corner Code <u>##</u>
1. Public Land Survey	T <u>1S</u> R <u>6E</u>	<u>1-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber 00001 Page 0667 RM

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JOHN JEKABSON, in a field survey on 23 September, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1819 G.L.O. - T. WAMPLER SET POST	B. Walnut, 23"	S 22° W .07ch
	W. Oak, 12"	N 17° E .33ch
Date Unknown PETTIBONE	W. Oak, 22"	N 75° E .42ch
	W. Oak, 20"	S 75½° E .67ch.

SEE BACK OF THIS SHEET (NEXT PAGE)
 FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BOAT SPIKE AT ASPHALT SURFACE OF ROAD.
 6" BELOW ASPHALT SURFACE FOUND 2ND BOAT SPIKE IN 1½" IRON
 USING 5 WITNESSES FROM SECTION "A"

SURVEY &
 MONUMENTATION

MAY 05 1997

COMMISSION

COPY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET MON BOX	SE Leg of D.E. Tower #9983 at base	N 40° W	161.75	13
SET IRON WITH REMON. CAP	PK & RT in NW sd. Wd. Pole N sd Gate	N 30° E	99.20	14
OVER THE 1½" IRON PIPE IN	C/L Stump	N 80° E	33.8	9'
MON BOX	Center of 15" Hickory	East	73.3	6'
	Northerly Gate Post	S 70° E	35.4	12'
	PK & RT in SW sd. 16" Oak	S 40° E	53.99	7'
	Found Iron Pipe (R/W)	West	33.00	10'



I conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by I. John Jekabson Date 11 NOVEMBER, 1996

Surveyor's Michigan License No. 19836

Continuation of Section "A"
 1996 WASHTENAW COUNTY REMONUMENTATION PROGRAM
 NORTHFIELD TOWNSHIP TOWN 1 SOUTH, RANGE 6 EAST
 I-12 (1/4 CORNER COMMON TO SECTIONS 34 & 35)

History compiled by:
 I. John Jekabson P.S. # 19836
 Roskelly, Jekabson & Assoc. P.C.

DATE	COMPANY SURVEYOR & P.S. #	JOB #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1959 25 June	WASHTENAW CO. ROAD COMMISSION Hand written in Grid Book R.B.					Nail in 10" Hickory Nail in 14"W. Oak Nail in 10" Elm Center of 2"Walnut R.W. Pipe East East S 40° E N 30° W N 80° E	54.90 60.00 35.80 25.65 33.00 73.4 53.9 66.8 30.6	1 2 3 4 5 6 7 8 9	
Unknown	ATWELL-HICKS, INC. Hand written in Wash. Co. Rd. Comm. Grid Book					10" Hickory 14"W. Oak T.P. 2" Hickory	73.4 53.9 66.8 30.6	6 7 8 9	
1972 14 June	ATWELL-HICKS, INC. HOWARD W. TAFT # 12032	503-20		S.W. 1/4 Section 35	Found 1" I.P.	13" Hickory 18" Oak R.O.W. Pipe	73.3 53.9 33.0	6* 7* 5*	
1973 12 Sept.	WASHTENAW ENG. CO. NORMAN N. FAHRNER #17620	11084		S.W. 1/4 Section 35	F - Spike	R.O.W. Pipe 10" Hickory 14"W. Oak 2" Hickory	33.0 73.4 53.9 30.6	5* 6* 7* 9*	
1973 17 Sept.	WASHTENAW ENG. CO JOHN F. OLIVER #19840				Found Boat Spike	Same as 1973, 12 September			
1974 23 Dec.	WASHTENAW ENG. CO. NORMAN N. FAHRNER #17620	12647		S.W. 1/4 Section 35	Found - Spike	Same as 1973, 12 September			
1976 23 June	WASHTENAW ENG. CO. NORMAN N. FAHRNER #17620	14017		S.W. 1/4 Section 35	Found - Spike	Same as 1973, 12 September			
1976 29 Sept.	ASSOCIATED ENGRS. & SURVEYORS, INC. GLENN RICHARD # 13040	760813		N.W. 1/4 Section 35	SPK.	I.P. 14" Hickory 18" Oak	33.00 73.3 53.9	10 6* 7*	
1979 12 October	METRO ENGINEERS, INC. MORRIS LEVINE #11076	Not legible		S.W. 1/4 Section 35	Found Boat-Spike	Nail & Tag W.D. Post at S. sd. Gate Nail & Tag 18" Oak Northerly Gate Post Pipe S. Line Edison Easement	83.42 53.06 35.4 33.00	11 7* 12 10*	
1988 5 June	WASHTENAW ENG. CO T.L. SUTHERLAND # 24620	21912		S.W. 1/4 Section 35	Found - Spike	Same as 1973, 12 September			

* INDICATES PREVIOUSLY USED