

APPROVED

DATE 10-28-96

CO. REP. KA

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
WASHTENAW COUNTY,
FEB 18 9 20 AM '97
PEGGY M. HAINES
COUNTY CLERK/REGISTRAR

For corners in

WASHTENAW
(County)

Located In:

Corner Code #

- 1. Public Land Survey T1S R 6E J-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Liber 00001 Page 0663 RM

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, I. JOHN JEKABSON, in a field survey on 20 August, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1819 G.L.O. - SET B. Oak, 24" S 89° E .48ch
POST Aspen, 28" S 67° W .12ch
T. WAMPLER

Grid table with columns A-M and rows 2-13. A circled 'X' is located at row 9, column J.

COPY

SEE BACK OF THIS SHEET (NEXT PAGE) FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 18" IRON PIPE
USING 5 WITNESSES FROM SECTION "A"

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" x24" Iron Pipe with Remon Cap PK & RT in S sd in 12" Basswood N 88° W 10.04 6"
Center 8" Cherry N 05° W 5.4 5"
PK & RT in N sd 30" Oak S 88° E 19.72 1"
PK & RT in SE sd 16" Shagbark Hickory S 45° W 37.35 3"
PK & RT in S sd 24" Oak S 75° W 32.29 4"

I conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by [Signature] Date 11 NOVEMBER, 1996

Surveyor's Michigan License No. 19836



CONTINUATION OF SECTION "A"

1996 WASHTENAW COUNTY REMONUMENTATION PROGRAM
NORTHFIELD TOWNSHIP TOWN 1 SOUTH, RANGE 6 EAST
J-9 (1/4 CORNER COMMON TO SECTIONS 23 & 26)

History compiled by: I. John Jekabson P.S. # 19836
Rostkelly, Jekabson & Assoc. P.C.

DATE	COMPANY SURVEYOR & P.S. #	JOB #	P.A. 74 L.C.R.C. OF SURVEY MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1967	LOKEY ENGINEERING & SURVEYING CO.		No indication	No witnesses			
1 November 1985	WILBURN B. LOKEY #9434	35967	N.E. 1/4 Section 26	30" Oak	S 83° E 20.1	1	
17 April 1989	ATWELL-HICKS, INC. ROBERT G. MACOMBER # 27453		Fd. 1/2" Iron Pipe @ N-S-E-W Fenceline Intersection	16" Shagbark Hickory 16" Twin Shagbark Hickory 20" Oak	S 20° W 29.7 S 40° W 38.7 S 75° W 32.5	2 3 4	
11 May 1989	CORNERSTONE Surveying & Engineering Inc. GILBERT G. BONNO #32332		S.E. 1/4 Section 23	6" Black Cherry 12" Basswood 16" Shagbark Hickory 30" Oak	N 05° W 5.40 West 10.00 S 45° W 37.63 East 19.90	5 6 3* 1*	
11 May 1989	CORNERSTONE Surveying & Engineering Inc. GILBERT G. BONNO #32332		Found 3/4" Pipe	Same as above			
7 August 1989	KOSTECKE & ASSOC. INC RAYMOND J. KOSTECKE #12584	89-6281	S.E. 1/4 Section 23	6" Black Cherry 12" Basswood 30" Oak	N 05° W 5.40 West 10.00 East 19.90	5* 6* 1*	
6 April 1993	C. WILSON & ASSOCIATES, INC. CHARLES C. WILSON #13604	92035	East 1/2 Section 26	6" B. Cherry 12" Basswood 16" Hickory 30" Oak	N 05° W 5.40 Wly 10.00 S 45° W 37.63 Ely 19.90	5* 6* 3* 1*	

* INDICATES PREVIOUSLY USED