

REGISTRATION

MAY 05 1997

APPROVED
DATE 11-11-96
CO. REP. KA

COMMISSION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
WASHTENAW COUNTY, MICH.
FEB 18 9 12 AM '97
PEGGY A. HAINES
COUNTY CLERK/REGISTER

For corners in
Washtenaw
(County)

Located in: _____ Corner Code # _____

1. Public Land Survey
T 1s R 7E _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling
in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous
Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Liber 00001 Page 0616

Register of Deeds Stamp & File Number

I, Thomas Sutherland, in a field survey on 10/18, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, at in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | | |
|-------------|--------------------------|-------------|------|----|------------------------------------|
| 11/
1815 | G.L.O.
JOSEPH WAMPLER | FIELD NOTES | NONE | 1) | 16" HICKORY N12 1/2°
W 16 LINKS |
| | | | | 2) | 5" IRONWOOD S18 1/2°W
2 LINKS |

(SECTION A CONTINUED ON REVERSE SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FROM OLD WITNESSES (*)
FOUND BENT AND BROKEN BOAT SPIKE INSIDE OF 2" IRON PIPE. SET 3/4" X 18" IRON PIPE W/REMON CAP INSIDE AND OVER 2" IRON PIPE 6" BELOW GRAVEL SURFACE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.
- *4) SE CORNER OF HOUSE (FOOTING) N50°W 81.30
 - *5) 21" MAPLE N40°W 40.56 TO WCRP TAG ON NE SIDE
 - *8) TELEPHONE POLE S45°E 48.89 TO WCRP TAG ON NE SIDE
 - *9) NE CORNER OF HOUSE (FOOTING) S35°W 87.85

3/4" X 18" IRON PIPE W/REMON CAP INSIDE AND OVER 2" IRON PIPE 6" BELOW GRAVEL SURFACE (SECTION C CONTINUED ON REVERSE SIDE)

Signed by Thomas L. Sutherland
Surveyor's Michigan License No. Thomas L. Sutherland #24620

Date NOVEMBER 18, 1996

COPY

*OLD WITNESS FOUND

(CONTINUED FROM A. ON FRONT)

Date	Surveyor	Notes	Findings	Measurements
1/44	G.L.O. HENRY PARKE	FIELD NOTES	NONE	3) 6" APPLE N25 1/2°W 225 1/2 LINKS
1/25	W.C.R.C. E.J. ALLMENDINGER K.K. MADISON	GRID BOOK	WAGON SKEIN	*4) COR. HOUSE N'WLY 81.3 *5) 4" MAPLE N'WLY 40.5 6) DRILL HOLE IN BOULDER N'ELY 50.0 7) S'LY TO WIRE FENCE 33.0
1/13/72	WASHTENAW ENGINEERING NORMAN FAHRNER #17620	L.C.R.C. LIBER 1, PAGE 645	IRON PIPE	*4) CORNER HOUSE N'WLY 81.3 *5) 4" MAPLE N'WLY 40.5 6) DRILL HOLE IN BOULDER N63°E 50.0
5/07/72	WASHTENAW ENGINEERING NORMAN FAHRNER #17620	SURVEY R-2721	IRON PIPE	*4) CORNER OF HOUSE N58°W 81.3 *5) 12" MAPLE N35°W 40.5 6) HOLE IN BOULDER N63°E 50.0
1/11/74	ROSKELLY, JEKABSON ROBERT ROSKELLY #18663	SURVEY 73-10-14	RAILROAD SPIKE	6) HOLE IN BOULDER N63°E 49.84 *8) P.K. NAIL IN D.E. POLE S45°E 48.97 *9) NE CORNER OF HOUSE S20°W 87.87 *4) SE CORNER OF HOUSE N58°W 81.30
3/18/76	ATWELL-HICKS ROBERT JAGOW #6998	L.C.R.C. LIBER 4, PAGE 148	BOAT SPIKE IN 1" IRON PIPE	6) DRILL HOLE IN BOULDER N45°E 49.8 *5) 16" MAPLE N40°W 40.4 *4) HOUSE CORNER N55°W 81.3 10) NW HOUSE CORNER S30°W 81.9
7/27/77	WASHTENAW ENGINEERING THOMAS SUTHERLAND #24620	SURVEY R-3986	IRON PIPE	*4) CORNER OF HOUSE N58°W 81.3 *5) 12" MAPLE N35°W 40.5 6) HOLE IN BOULDER N63°E 50.0
5/05/82	ROSKELLY, JEKABSON ROBERT ROSKELLY #18663	SURVEY A-82-4-44	BOAT SPIKE	*8) PK NAIL IN D.E. POLE S45°E 48.79 *9) NE COR. HOUSE #9370 S20°W 87.87 *4) SE COR. HOUSE #6609 N58°W 81.30 *5) CENTER 15" MAPLE S35°W 40.50
7/20/87	WASHTENAW ENGINEERING THOMAS SUTHERLAND #24620	SURVEY R-5749	NONE	*4) HOUSE CORNER N58°W 81.3 *5) 12" MAPLE N35°W 40.5
8/09/89	NORMAN FAHRNER #17620	SURVEY R-5997		*8) P. POLE N40°E 48.87 TO NAIL 6) HOLE IN BOULDER N63°E 49.83 *11) P. POLE N60°E 56.87

R1

J-9 TIS R7E

(CONTINUED FROM A. ON FRONT & SHEET 1 OF 2)

01/03/95	ROSKELLY, JEKABSON JOHN JEKABSON #19836	SURVEY 91-11-84	BOAT SPIKE	6) HOLE IN BOULDER N63°E 49.84
				*8) NAIL IN D.E. POLE S45°E 48.79
				*9) NE COR. HOUSE S20°W 87.87
				*4) SE COR. HOUSE N60°W 81.30

(CONTINUED FROM C. ON FRONT)

*11) TELEPHONE POLE N60°E 56.91 TO WCRP TAG ON WEST SIDE	13) NW CORNER GARAGE S20°E 141.97
12) ELECTRIC POLE S43°E 45.60 TO WCRP TAG ON SW SIDE	14) SW CORNER BARN N70°E 180.00

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION