

SURVEY  
REMONUM

MAY 12 1987

APPROVED  
DATE 11-11-96  
CO. REF. KA

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

REC'D M. JAINES  
COUNTY CLERK/REGISTRAR

FEB 18 9 13 AM '97

RECORDED  
WASHTENAW COUNTY, MI

For corners in  
Washtenaw  
(County)

Located In:	Corner Code #
1. Public Land Survey	T <u>1S</u> R <u>7E</u> <u>J-13</u>
	T <u>   </u> R <u>   </u> <u>   </u>
	T <u>   </u> R <u>   </u> <u>   </u>
	T <u>   </u> R <u>   </u> <u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u> <u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u> <u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u> <u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u> <u>   </u>

Liber 00001 Page 0621pm

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas Sutherland, in a field survey on 10/18, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

10/18/ G.L.O. FIELD NOTES SWAMP POST  
1815 JOSEPH WAMPLER

- 1) 8" Ash S56°W 6 Links
- 2) 20" Maple East 8

(SECTION A CONTINUED ON REVERSE SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND OLD WITNESSES (\*)

FOUND 1 1/2" IRON PIPE 3" BELOW GRAVEL SURFACE. FOUND BRICKS 12" BELOW GRAVEL SURFACE. SET REMON CAP IN EXISTING PIPE 6" BELOW GRAVEL SURFACE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I conclude that after careful study of the record documentation and field observations, that this corner is accepted as a careful and faithful perpetuation of the position of the original corner.

- \*8) 1 1/2" IRON PIPE NORTH 32.87
- \*10) NORTH EDGE TRAVELED ROAD NORTH 10.5
- \*15) WEST END 9" STEEL CULVERT S 78°E 90.45
- \*16) 16" TWIN ASH S54°W 60.80 TO WCRP TAG ON NW SIDE

1 1/2" IRON PIPE W/REMON CAP 6" BELOW GRAVEL SURFACE. (SECTION C CONTINUED ON REVERSE SIDE)

Signed by Thomas E. Sutherland  
Surveyor's Michigan License No. THOMAS E. SUTHERLAND #24620

Date NOVEMBER 13, 1996

COPY

\*OLD WITNESS FOUND

(CONTINUED FROM A ON FRONT)

01/26/49	UNKNOWN J.F. DAoust	GRID BOOK	1 1/2 X 5' IRON PIPE	*5) SPIKE IN SOUTH SIDE 36" MAPLE N5°W 12.83 6) SPIKE IN S SIDE 12" ELM S70°E 38.98 *7) SPIKE IN W. SIDE 9" OAK SOUTH 29.70
11/09/87	ATWELL-HICKS ROBERT MACOMBER #27453	SURVEY 503-197	1 1/2" IRON PIPE	*5) 60" MAPLE (SPIKE) N05°W 12.83 *7) 12" STUMP SOUTH 29.7 *8) 16" MAPLE (SPIKE) S50°W 38.7 9) 18" COTTONWOOD N70°E 59.7
01/09/90	WASHTENAW ENGINEERING H. LAWRENCE O'DONNELL #28419	SURVEY R-6060	1 1/2" IRON PIPE	*5) 48" MAPLE N05°W 12.75 TO NAIL *10) 12" ASH S85°W 12.39 TO NAIL *11) 16" MAPLE S30°W 28.34 TO NAIL

(CONTINUED FROM C. ON FRONT)

\*10) 12" ASH S85°W 12.39  
TO WCRC TAG ON SOUTH  
SIDE

\*11) 16" MAPLE S30°W 28.34  
TO WCRC TAG ON EAST  
SIDE

\*12) 16" ELM N35°W 15.47  
TO WCRC TAG ON NE SIDE

\*13) 28" OAK S75°E 74.86 TO  
WCRC TAG ON NE SIDE