

**SURVEY &
REMONUMENTATION**

MAY - 1 1995

COMMISSION

COPY

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED
WASHTENAW COUNTY, MI

JAN 10 9 50 AM '95

PEGGY M. HAINES
COUNTY CLERK/REGISTER

-COPY-

LIBER 1 PAGE 330 RM

-COPY-

Register of Deeds Stamp & File Number

For corners in

<u>Washtenaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1S</u> R <u>7E</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Thomas L. Sutherland in a field survey on December 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(Irvin E. Chope #6504 1969)
Homestead Acres Subdivision
Liber 19 of Plats, Page 43 &
44, Washtenaw County Records
Concrete Monument
Centerline Napier Road
N88°06'18"E 940.60

(Brender-Hamill 1974)
McClelland Subdivision
Liber 20 of Plats,
Page 9, Washtenaw
County Records
Centerline Napier Road
N88°00'42"E 940.60

(Ambit Land Surveyors 1988)
Concrete Monument
P.K. Nail in E. Face 10"
Fence Post N10°W 1.57
Steel Bar - #17022
EAST 7.10
Nail in N. Face of Utility
Pole EAST 27.04
Nail in E. Face of Utility
Pole S25°E 58.76

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Concrete Monument
in Range of Fence line
to the North.

APPROVED

DATE 12/15/94
CO. REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Concrete Monument
10" Fence Post N05°W 1.53 to
Nail W/W.C.R. Tag in E. Side
Iron Pipe in centerline Napier
Road EAST 940.51
3/8 Rod EAST 26.17
Power Pole S87°E 27.07 to Nail
W/W.C.R. Tag
Iron Rod (used by Boss
Engineering and others as
1/4 Corner) EAST 7.15
Steel Fence Post S75°E 7.02
Steel Fence Post S50°W 4.08

Power Pole S88°W 122.36 to Nail
W/W.C.R. Tag in E. Side
6" Spruce S10°E 32.94 to Nail
W/W.C.R. Tag
6" Spruce S30°W 37.32 to Nail
W/W.C.R. Tag
12" Pine S65°E 42.22 to Nail
W/W.C.R. Tag

I conclude that after careful study of the record documentation and field observation, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by [Signature]
Thomas L. Sutherland
Surveyor's Michigan License No. #24620

Date December 15, 1994