

**SURVEY &  
REMONUMENTATION**

MAY - 1 1995

**COMMISSION**

**COPY**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED  
WASHTENAW COUNTY, MI

JAN 10 9 51 AM '95

PEGGY M. HAINES  
COUNTY CLERK/REGISTER

For corners in

Washtenaw

(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>1S</u>	R	<u>7E</u>	<u>L-11</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

-COPY-

LIBER 1 PAGE 331 RM

- COPY -

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Thomas L. Sutherland in a field survey on November 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(Roskelly and Jekabson 1977-1993)

- Nail in 10" Hickory NORTH 18.67
- Nail in 11" Oak N35°E 11.30
- Nail in 9" Ash EAST 15.17
- Nail in 11" Ash S20°W 26.29
- Nail in 15" Ash S45°W 26.40

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Galvanized Iron Pipe at East Edge Rock in Fence Line (in poor repair) North and West. Set Remonumentation Cap on Existing Pipe and re-witnessed.

APPROVED

DATE 11/21/94

CO. REP. K

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1" Galvanized Iron Pipe with Aluminum Washtenaw County Remonumentation Cap
- 12" Hickory NORTH 18.67 to Nail W/W.C.R. Tag on E. Side
- 14" Oak N35°E 11.30 to Nail W/W.C.R. Tag on W. Side
- 14" Ash EAST 15.17 to Nail W/W.C.R. Tag on S. Side
- 18" Ash S40°W 26.29 to Nail W/W.C.R. Tag on N.W. Side
- 11" Ash S20°W 26.16 to Nail W/W.C.R. Tag on E. Side
- 12" Elm S10°E 9.15 to Nail W/W.C.R. Tag on E. Side

I conclude that after careful study of the record documentation and field observation, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by

Thomas L. Sutherland

Date

December 12, 1994

Surveyor's Michigan License No. #24620