

**SURVEY &  
REMONUMENTATION**

MAY - 1 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
WASHTENAW COUNTY, MI

I-12 Page

SEP 21 11 22 AM '94

PERCY H. HAINES  
COUNTY CLERK/REGISTER

COPY

LIBER

1 PAGE 85Rm  
-COPY-

Register of Deeds Stamp and File Number

For corners in

Washtenaw

County

Located in: Lima Twp Corner Code

1. Public Land Survey	T	2	S	R	4	E	I-12
	T			R			
	T			R			
	T			R			
2. Property Controlling in Section	S		T	R			
	S		T	R			
3. Miscellaneous Property in Sec.	S		T	R			
	S		T	R			
4. Lot No. _____, Recorded Plat _____							
5. Private Claims _____							

I, Michael S. Hoben in a field survey on Monday, January 11, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management. or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restorations:**

Friday, February 05, 1988 C. A. Eckfeld 33135 CWA L7-P15 Fd. 15" sq. conc pillar & axle.  
Witnesses:  
1 6" OAK S 74 W 23.14' TO NAIL  
2 18" OAK S 12 E 30.58' TO NAIL  
3 6" OAK S 55 E 11.46' TO NAIL  
4 12" OAK N 40 W 13.29' TO NAIL

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


Fd. 5" sq conc pillar & axle. Set WCR cap.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Monday, January 11, 1993 Orchard, Hiltz & McCliment, Inc. 21584 OHM W. C. Remon  
Witnesses:  
1 6" OAK S 74 W 23' (FALLEN TREE)  
2 18" OAK S 7 E 30.20' TO PK NAIL WITH WCR TAG.  
3 6" OAK S 51 E 11.17' TO PK NAIL WITH WCR TAG.  
4 12" OAK N 40 W 13.30' TO PK NAIL WITH WCR TAG.  
5 15" OAK N 54 W 16.20' TO PK NAIL WITH WCR TAG.

We conclude that after careful study of the record documentation and field observations that this corner is accepted as the best available evidence of the position of the original corner.

I-12 Page 2



**APPROVED**

DATE 3-22-94

CO. REP. HA

Signed by Michael S. Hoben  
Drafted by Michael S. Hoben  
Surveyor's Michigan License No. 35994

Aug 2 1994