

**SURVEY &
REMONUMENTATION**

MAY - 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Washtenaw
County

Located in: Lima Twp Corner Code

1. Public Land Survey	T <u>2</u> S	R <u>4</u> E	<u>K-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

K-13
 REGENT M. HAINES
 COUNTY CLERK/REGISTER
 WASHINGTON COUNTY, MI
 RECORDED
 SEP 21 11 25 AM '94
 101RM
 COPY
 Register of Deeds Stamp and File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Michael S. Hoben in a field survey on Monday, November 01, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management. or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restorations:

- | | | | | | |
|---|-----------------|-------|------------|-----------------------|--|
| Monday, January 01, 1816 | B. Hough | | | G.L.O. | 1815 - 1816. Set post. |
| Witnesses: | | | | | |
| 14" SYCAMORE N. 24 E., 41 LINKS (27.06') | | | | | |
| 12" ASH S. 13 W., 24 LINKS (15.84') | | | | | |
| Thursday, May 04, 1939 | W. J. Armstrong | 2444 | WCRC | Grid Book | See Book 144, P 141 Restored in center of highway, set 1 1/2" X 40" iron pipe. |
| Witnesses: | | | | | |
| 1 20" ELM N. 5.5 W., 52.7' | | | | | |
| 2 14" APPLE S. 14 E., 55.8' | | | | | |
| 3 16" B. CHERRY S. 37.5 W., 37.0' | | | | | |
| 4 24" W. OAK S. 53 W., 51.3' | | | | | |
| Monday, October 28, 1974 | Howard W. Taft | 12032 | | L3-P56 | Fd. 1 1/2" pipe & 2 witnesses. |
| Witnesses: | | | | | |
| 2 APPLE S. 14 E., 55.9' | | | | | |
| 4 32" W. OAK S. 47 W., 51.3' | | | | | |
| 5 N.E. COR. TOWNSHIP HALL S. 27 W., 69.2' | | | | | |
| 6 30" W. OAK S. 50 W., 68.3' | | | | | |
| 7 MON. BOX S. 89 W., 29.05' | | | | | |
| Saturday, September 17, 1983 | R. A. Campbell | 13028 | | L6-P30 | Fd 1/2" pipe Set 3/4" X 18" iron pipe @ road surface. |
| Witnesses: | | | | | |
| 8 SET NAIL IN E/SIDE 30" OAK S. 60 E., 67.13' | | | | | |
| 9 SET NAIL IN E/SIDE 6" BASSWOOD SOUTH 36.45' | | | | | |
| 10 SET NAIL IN S/SIDE COR. WOOD FP N. 67 E., 93.62' | | | | | |
| 11 5" ELM S. 67 E., 47.0' | | | | | |
| 12 N. EDGE PAVE. NORTH 14.6' | | | | | |
| 13 S. EDGE PAVE. SOUTH 9.2' | | | | | |
| Saturday, January 30, 1988 | C. A. Eckfeld | 33135 | C. Willson | Certificate of Survey | Fd. 3/4" iron pipe. |
| Witnesses: | | | | | |
| 4 32" W. OAK S. 54 W., 51.32' | | | | | |
| 5 N.E. COR. TOWNSHIP HALL S. 27 W., 69.2' | | | | | |
| 7 IRON PIPE S. 89 W., 29.13' | | | | | |
| 14 FENCE POST N. 47 W., 66.08' | | | | | |
| 15 UTILITY POLE N. 38 E., 54.40' | | | | | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1" iron pipe & installed a mon. box and set a WCR cap on Fd. iron

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monday, November 01, 1993

Orchard, Hiltz &
McCliment, Inc.

21584


OHM

LIBER 1 PAGE 102 Bm
-copy- K-13 Page 2
W.C. Remon

Witnesses:

- 4 SET A PK NAIL WITH A WCR TAG IN A 42" OAK S. 63 W., 50.84'
- 15 SET A PK NAIL WITH A WCR TAG IN A D.E. POLE N. 41 E., 54.41'
- 16 SET A PK NAIL WITH A WCR TAG IN A D.E. POLE N. 36 W., 71.70'
- 17 SET A PK NAIL WITH A WCR TAG IN A D.E. POLE S. 5 E., 32.12'

We conclude that after careful study of the record documentation and field observations, that this corner is accepted as a careful and faithful perpetuation of the position of the original corner.



Signed by Michael S. Hoben

Drafted by Michael S. Hoben

Surveyor's Michigan License No. 35994

Date Aug 6, 1994

Orchard, Hiltz and McCliment, Inc. 34935 Schoolcraft Road Livonia, MI 48150

APPROVED

DATE 4-19-74

CO. REP. ES