

**SURVEY & REMONUMENTATION**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Washtenaw  
County

Located in: Lima Twp Corner Code

1. Public Land Survey	T	2	S	R	4	E	L-11
	T			R			
	T			R			
	T			R			
2. Property Controlling In Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

RECORDED  
 WASHTENAW COUNTY, MI  
 SEP 21 11 26 AM '94  
 PERCY M. HAINES  
 COUNTY CLERK/REGISTER  
 L-11  
 1 PAGE  
 104RM  
 REGISTER OF DEEDS STAMP AND FILE NUMBER  
 COPY

I, Michael S. Hoben in a field survey on Monday, November 01, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restorations:**

- Wednesday, January 01, 1817 Wampler G.L.O. After 1816. Set post.  
Witnesses:  
26" W. OAK N. 65 E., 16 LINKS (10.56')  
22" WHITE OAK N. 84 W., 24 LINKS (15.84')
- Wednesday, May 26, 1937 W. J. Armstrong 2444 WCRC Grid Book Fd. old wood stake. Set 1 1/2" X 36" iron pipe with stones & bricks.  
Witnesses:  
1 HICKORY 16" DIA. S. 79.5 E., 157.8'  
2 HICKORY 16" DIA. S. 2.5 W., 286.2'  
3 HICKORY 14" DIA. S. 3 W., 263.7'
- Tuesday, January 07, 1975 Howard W. Taft 12032 L.3,P.5 Fd. 1 1/2" iron pipe.  
Witnesses:  
1 HICKORY 24" DIA. S. 79.5 E., 157.9'  
2 HICKORY 24" DIA. S. 2.5 W., 286.2'  
3 HICKORY 24" DIA. S. 3 W., 263.7'  
4 POWER POLE #327 N. 20 W., 28.8'


**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Fd 1 1/2" iron pipe & set WCR cap on iron.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Monday, November 01, 1993 Orchard, Hiltz & McCliment, Inc. 21584 OHM W. C. Remon  
Witnesses:  
1 STUMP 24" DIA. S. 79.5 E., 157.0'  
2 HICKORY 24" DIA. S. 2.5 W., 286.2'  
3 HICKORY 24" DIA. S. 3 W., 263.7'  
5 PK NAIL WITH WCR TAG IN D.E. POLE S. 65 E., 44.00'  
6 PK NAIL WITH WCR TAG IN TWIN 6" TREE S.3 W., 64.30'  
7 PK NAIL WITH WCR TAG IN D.E. POLE S. 86 W., 87.47'  
8 PK NAIL WITH WCR TAG 8" TREE N. 9 W., 38.98'

We conclude that after careful study of the record documentation and field observations, that this corner is accepted as a careful and faithful perpetuation of the position of the original corner.



APPROVED  
DATE 5-31-94  
CO. REP. K

Signed by Michael S. Hoben  
Drafted by Michael S. Hoben  
Surveyor's Michigan License No. 35994

Date Aug 2 1994