

SURVEY & REMONUMENTATION

MAY - 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Washtenaw
County

Located in: Lima Twp Corner Code

- | | | | | | |
|---------------------------------------|---------|--------------|--------------|-------|-------|
| 1. Public Land Survey | | T <u>2</u> S | R <u>4</u> E | | M-9 |
| | | T _____ | R _____ | _____ | _____ |
| | | T _____ | R _____ | _____ | _____ |
| | | T _____ | R _____ | _____ | _____ |
| 2. Property Controlling
In Section | S _____ | T _____ | R _____ | _____ | _____ |
| | S _____ | T _____ | R _____ | _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ | T _____ | R _____ | _____ | _____ |
| | S _____ | T _____ | R _____ | _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

COPY

RECORDED
WASHTENAW COUNTY, MI

SEP 24 11 26 AM '94

PAGE 107 RM

-COPY-

REGISTER OF DEEDS STAMP AND FILE NUMBER

I, Michael S. Hoben in a field survey on Monday, November 01, 1993
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

1. Description of original monument and accessories and/or subsequent restorations:

- Monday, January 01, 1816 Fletcher G.I.O. 1816. Set post.
Witnesses:
12" W. OAK S. 35 W., 72 LINKS (47.52')
12" W. OAK N. 68 W., 124 LINKS (81.84')
- Wednesday, June 08, 1932 W. J. Armstrong 2444 WCRC Grid Book Fd. wood stake & a group of stones. Reset with 1 1/2" X 40" iron pipe and placed 4 bricks around it.
Witnesses:
1 MAPLE 14" DIA. S. 34 W., 40.9'
2 NAIL IN BURR OAK 28" DIA. N. 62 W., 61.0'
3 NAIL IN BURR OAK 15" DIA. N. 84.5 E., 24.9'
4 NAIL IN MAPLE 24" DIA. S. 38.5 E., 49.0'
5 NAIL IN OAK 12" DIA. S. 80 W., 94.3'
6 NAIL IN OAK 24" DIA. N. 72.5 W., 100.25'

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1. 1/2" iron pipe in pave & set a on. box with WCR cap on iron.

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Monday, November 01, 1993 Orchard, Hiltz & McCliment, Inc. 21584 OHM W.C. Remon
Witnesses:
2 PK NAIL WITH WCR TAG IN OAK 48" DIA. N. 57 W., 60.88'.
4 PK NAIL WITH WCR TAG IN 20" OAK S. 33 E., 49.35'.
6 PK NAIL WITH WCR TAG IN OAK 42" DIA. N. 68 W., 99.38'.
7 PK NAIL WITH WCR TAG IN OAK 20" DIA. S. 51 E., 36.60'.

APPROVED
DATE 4-19-94
CO. REP. K

We conclude that after careful study of the record documentation and field observations that this corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Michael S. Hoben
rafted by Michael S. Hoben
urveyor's Michigan License No. 35994 Date Aug 2 1994

