

REMONUMENTATION

MAY - 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 108F
- COPY -
M-10 Page
SEP 21 11 26 AM '94
RECORDED
WASHTENAW COUNTY, MI
PEGGY H. HAINES
COUNTY CLERK/REGISTER

For corners in
Washtenaw
County

Located in: Lima Twp Corner Code

1. Public Land Survey	T 2 S R 4 E	M-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp and File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Michael S. Hoben in a field survey on Monday, November 01, 1993
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management. or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restorations:

Monday, January 01, 1816	Fletcher			G.L.O.	Set post.
Witnesses:					
16" B. OAK S. 24 W., 275 LINKS (181.50')					
12" B. OAK S. 85 W., 183 LINKS (119.78')					
Monday, April 09, 1934	W. I. Armstrong	2444	WCRC	Grid Book	Fd. traces of old wood stake. Reset with 1 1/2" X 48" iron pipe & put stones and bricks around it.
Witnesses:					
1 NAIL IN 10" ELM S 73 E., 32.2'					
2 30" W. OAK S. 11 E., 49.7'					
3 40" W. OAK S. 40 W., 40.0'					
4 NAIL IN 30" ASH S. 89 W., 45.4'					
5 8" WALNUT N. 16 W., 65.0'					
6 ROW IRON PIPE WEST 33.0'					
Tuesday, September 01, 1964	R. B.		WCRC	Grid Book	Fd. boat spike.
Witnesses:					
7 NAIL IN WOOD FENCE POST S. 70 W., 63.88'					
8 NAIL IN 4" POPLAR S. 36 E., 86.5'					
9 R.R. TIE END POST N. 86 E., 33.9'					
10 DRIVE CULV. NORTH END S. 38 E., 36.15'					
11 DRIVE CULV. SOUTH END S. 50 W., 30.83'					
12 IRON PIPE WEST 33'					
Monday, January 08, 1990	R. A. Campbell	13028	WCRC	L7-P24	Fd. 3/4" iron pipe raised to surface with PK nail.
Witnesses:					
9 R.R. TIE END POST N. 86 E., 33.9'					
10 DRIVE CULV. NORTH END S. 38 E., 36.0'					
11 DRIVE CULV. SOUTH END S. 50 W., 30.7'					
13 NAIL TO 6" B. OAK WEST 41.53'					


3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1/2" boat spike in pave. Set a
2" X 24" iron rebar with mon. box
with WCR tag on iron.

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monday, November 01, 1993	Orchard, Hiltz & McCliment, Inc.	21584	OHM	W. C. Remon
Witnesses:				
9 PK NAIL WITH WCR TAG 8" X 8" FENCE POST N.89 E., 34.07'				
13 PK NAIL WITH WCR TAG TO 10" B. OAK N. 81 W., 41.47'				
14 PK NAIL WITH WCR TAG IN TWIN 8" ELM N. 37 E., 62.75'				
15 PK NAIL WITH WCR TAG IN 10" BEECH S. 24 E., 57.12'				

We conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.



- COPY -

Signed by Michael S. Hoben Date Aug 2, 1994
Drafted by Michael S. Hoben
Surveyor's Michigan License No. 35994

Orchard, Hiltz and McCliment, Inc. 34935 Schoolcraft Road Livonia, MI 48150

APPROVED
DATE 5-31-94
CO. REP. K