

REI

SECTION

2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Washtenaw
(County)

Located In:

Corner Code #

1. Public Land Survey

T 2S R 5E

I-1

Copy

T ___ R ___

T ___ R ___

T ___ R ___



5094717
Page: 1 of 1
02/07/2000 02:55P

2. Property Controlling
in Section

S ___

T ___ R ___

S ___

T ___ R ___

3. Miscellaneous

S ___

T ___ R ___

Property in Section

S ___

T ___ R ___

Peggy M. Haines - Washtenaw Co. CORREM L-2 P-308

Register of Deed Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas L. Sutherland, in a field survey on 11-18-1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent resortation: 13

- G.L.O. 1819, Field Notes
- 18" B.O. S3°W 9 Links
- 20" B.O. N4°W 50 Links

As shown on plat of "Loch Alpine" dated 1929 I-13, T1S, R5E Westerly 376.20

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 4" steel encased concrete monument stamped L.A. 16" above ground on the Northwesterly side of a hill.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 4" steel encased concrete monument stamped L.A. 16" above ground on the Northwesterly side of a hill.
- 24" Oak North 13.57 to remon tag on W. Side
- 5" Ash S80°W 2.55 to remon tag on N. Side
- 7" Ash S10°E 7.27 to remon tag on W. Side
- 7" Ash S55°E 12.69 to remon tag on SW Side
- 38" Oak East 25.33 to remon tag on N. Side
- 4" Steel encased concrete monument stamped L.A. (I-3, T1S, R5E) West 375.19

I conclude after careful study of the record documentation and field observation, that this corner is accepted as the best available evidence of the position of the original corner. This corner is not common to I-13, T1S, R5E.

Signed by:

Thomas L. Sutherland

THOMAS L. SUTHERLAND

Date

12/20/99

Surveyor's Michigan License No.

24620

APPROVED
DATE 12/13/99
CO. REP. K

