

REM

JAN 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Washtenaw
(County)

Located In:

Corner Code #

1. Public Land Survey

T 2S R 5E I-10

T ___ R ___

T ___ R ___

T ___ R ___

Peggy M. Haines - Washtenaw Co. CORREM

5094726
Page: 1 of 1
02/07/2000 02:55P
L-2 P-324

2. Property Controlling
in Section

S ___

T ___ R ___

S ___

T ___ R ___

3. Miscellaneous
Property in Section

S ___

T ___ R ___

S ___

T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deed Stamp & File Num

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas L. Sutherland, in a field survey on 11-8-1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent resortation:

G.L.O. 1819, Field Notes
1) 17" B.O. N18°E 51 Links

Handwritten in Grid Book, No Date
"Concrete Fence Corner Used by Atwell-Hicks

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 9 1/2" (N-S) by 7" (E-W) concrete fence post leaning Southeasterly. Post was solid but the ground around the bottom appeared to have been disturbed at one time. Fence lines run North, South, East, and West. Witnesses are to bottom center of post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

9 1/2"(N-S) by 7" (E-W) concrete fence post leaning southeasterly. Witnesses are to bottom center of post.

- 18" Cherry N85°W 5.70 to remon tag on N. Side
- 18"-14" Twin Cherry West 17.41 to spike on N. Side
- 15" Cherry North 49.95 to remon tag on E. Side
- 12" Elm N85°E 16.27 to spike on N. Side
- 18" Cherry East 32.38 to remon tag on N. Side
- 6" Cherry S5°W 30.26 to remon tag on E. Side

APPROVED
DATE 12/16/99
CO. REP. KE

I conclude after careful study of the record documentation and field observation, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by: Thomas L. Sutherland Date: 12/17/99

Surveyor's Michigan License No. 24620 No. 24620

