

REF

2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Washtenaw (County) Located In: Corner Code #
1. Public Land Survey T 2S R 5E J-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. Recorded Plat
5. Private Claims



+ Copy - Register of Deed Stamp & File Number

I, Thomas L. Sutherland, in a field survey on 11-15-1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. Cell (4,11) contains a black dot.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent resortation:

- G.L.O. 1819, Field Notes
1) 17" W. Oak S15°E 69 Links
2) 44" W. Oak N80°W 60 Links

Continued on Back

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 3/4" x 16" gas pipe 8" below Easterly edge of gravel surface above 1/4" x 1 1/2" x 6" iron strap, above iron rod inside and above 1/2" iron pipe 26" below surface surrounded by large rocks and brick fragements. Set 1" x 24" iron pipe with aluminum remonumentation cap stamped 24620 over rod and 1/2" iron pipe 6' below surface. Replaced rocks around new pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1" x 24' iron pipe with aluminum remonumentation cap stamped 24620 6" below Easterly edge of gravel surface, over existing iron rod and 1/2' iron pipe surrounded by rocks. Stub of broken PK nail in chiseled hole of concrete drive apron
7) Power pole N85°E 34.39 to remon tage on N. Side
8) Power Pole West 39.71 to PK on S. Side
9) 18" Oak S40°E 30.92 to remon tag on SW Side
10) 30" Oak S40°W 74.83 to remon tag on NW Side
11) 36" Oak S35°W 95.41 to remon tag on SE Side
14) 30" Oak N30°E 65.25 to remon tag on NW Side
15) 12" Walnut N40°W 43.36 to remon tag on SW Side

I conclude after careful study of the record documentation and field observation, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by: [Signature] THOMAS L. SUTHERLAND
Surveyor's Michigan License No. 24620

12/20/99

APPROVED DATE 12/13/99 CO. REF. [Signature]

A. Continued

H.H. Atwell #322, No Date, Grid Book
Iron Pipe

- 3) 14" Elm S54 1/2°W 46.7
- 4) 16" Elm N77°W 28.4
- 5) 6" B. Oak N17 1/2°W 76.4
- 6) 7" W. Oak N14°W 76.4



5094732
Page: 2 of 2
02/07/2000 02:55P
L-2 P-336

Peggy M. Haines - Washtenaw Co. CORREM

- Copy -

Washtenaw Engineering, J.F. Oliver #19840, 3/1/74,
L.C.R.C. Liber 4, Page 101; 3/1/74, Survey R-3238;
N.N. Fahrner #17620, 6/21/76, Survey R-3733; 11/9/77,
Survey R-4039; 1/9/85, Survey R-5184; 7/2/88,
Survey R-5823
3/4" Iron Pipe

- 3) 30" Elm S54 1/2°W 46.7
- 7) Power Pole N88°E 34.5
- 8) Power Pole West 29.8
- 9) 8" Oak S40°E 31.0

REF

2000

SECTION

Atwell-Hicks, R.J. Jagow #6998, 6/30/76, L.C.R.C. Liber 4,
Page 146; 6/25/76, Survey 506-38; H.W. Taft # 12032,
2/16/77, Survey 506-49; R.S. Macomber #27453,
Survey 506-84A

3/4" Iron Pipe - "Witness Do Not Check. Verified from
1945 Survey by others.

- 10) 30" Oak S45°W 74.9
- 11) 36" Oak S40°W 95.4
- 12) Fence Corner West 34.0
- 7) Power Pole N85°E 34.6

Atwell-Hicks, R.J. Jagow #6998, 6/28/76, Survey 506-40;
6/7/79, Survey 507-94

3/4" Iron Pipe

- 7) Power Pole N85°E 34.6
- 12) Fence Corner West 34.0
- 13) 24" Elm Stump S50°W 60.0
- 10) 30" Oak S45°W 74.9
- 11) 30" Oak S40°W 95.4

Washtenaw Engineering, N.N. Fahrner #17620, 12/1/78,
Survey R-4275; 8/19/86, Survey R-5486; 6/17/97,
Survey R-7411

3/4" Iron Pipe

- 7) Power Pole N85°E 34.6
- 12) Fence corner West 34.0
- 13) 24" Elm stump S50°W 60.0
- 10) 30" Oak S45°W 74.9
- 11) 30" Oak S40°W 95.4

C. Wilson and Associates, C.C. Wilson # 13604, 3/10/86,
Survey 85204; 2/16/87, Survey 87032

3/4" Iron Pipe

- 3) 30" Elm S54 1/2°W 46.7
- 7) Power Pole N88°E 34.5
- 8) Power Pole W'y 29.8
- 9) 8" Oak S50°E 31.0