

REF: 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

or corners in

Washtenaw (County) Located In: Corner Code #

Public Land Survey T 2S R 5E J-7

Property Controlling in Section S _____ T _____ R _____

Miscellaneous Property in Section S _____ T _____ R _____

Lot No. _____, Recorded Plat _____

Private Claims _____



5094733
Page: 1 of 2
02/07/2000 02:55P
L-2 P-337

Peggy M. Haines - Washtenaw Co. CORREM

Copy - Register of Deed Stamp & File Number

I, Thomas L. Sutherland, in a field survey on 11-15-1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent resortation:

- G.L.O. 1819, Field Notes
- 1) 21" B.O. S16°E 24 Links
- 2) 20" B.O. N9°W 26 Links

Continued on Back

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1" Iron pipe 12" below gravel surface surrounded by bricks. Raised with 3/4" iron pipe with aluminum remonumentation cap stamped 24620 to 6" below gravel surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4" iron pipe with aluminum remonumentation cap stamped 24620 6" below gravel surface over 1" iron pipe 12" below surface surrounded by bricks.
- 3) SE Corner stone house N38°W 90.4
- 9) 36" Spruce N43°W 48.74 To PK on NE Side
- 11) 1" Iron Pipe North 32.94
- 13) 14" Cherry N46°E 44.01 to remon tag on SE Side
- 14) 14" Walnut S23°E 27.12 to remon tag on NE Side
- 15) Utility Pole South 23.26 to PK nail on E. Side
- 16) 28" Oak S25°E 29.54 to remon tag on NW Side
- 17) 16 Walnut S55°W 41.32 to remon tag on NW Side
- 18) Utility pole N2°W 52.93 To Nail
- 19) 14" Walnut N65°E 48.57 to remon tag on S'LY Side

I conclude after careful study of the record documentation and field observation, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by: Thomas L. Sutherland Date: 12/17/99

Surveyor's Michigan License No. 24620

APPROVED
DATE 12/13/99
CO. REP. Kx

A. CONTINUED

Grid Book, No Date

Large Stone with bricks around it

- 3) 91.1 from SE cor. house on N. Side of road
- 4) Norway Spruce N15°W 38.0

Grid Book (Handwritten), No Date

- 5) 40" Triple Elm N71°E 52.8
- 6) 36" Triple Elm S76°E 57.6
- 7) 6" B. Cherry S30°E 16.7
- 8) 30" Spruce N45°W 67.7
- 9) 28" Spruce N42°W 49.1

W.C.R.C., R.A. Campbell #13028, 5/1/80,
 L.C.R.C. Liber 5, Page 342
 (From 1936 W.C.R.C.)

Large Stone surrounded by Brick

- 5) 40" Triple Elm N71°E 52.8
- 6) 36" Triple Elm N76°E 57.6
- 7) 6" B. Cherry S30°E 16.7
- 10) 24" Spruce N71°W 102.9
- 8) 30" Spruce N49°W 67.7
- 9) 28" Spruce N42°W 49.1
- 3) SE Corner house N38°W 91.1
- 4) 32" Spruce N16°W 38.0

11 & 12) 2 R.O.W. Pipes
(From 1980 W.C.R.C. R.Campbell)

Found 1" Iron Pipe surrounded by brick

- 5) Remnants of stump N66°E 52.8±
- 6) Depression in Ground S73°E 57.6±
- 10) 38" Stump N70°W 102.7
- 9) 27" Spruce N43°W 49.3
- 3) SE Corner house N36°W 90.4
- 4) 34" Spruce N15°W 37.9
- 11) 1" Iron North 32.93
- 13) 7" Cherry N46°E 43.98 – Nail in NW Side
- 14) 9" Oak S23°E 27.1
- 15) U.P. S05°W 23.54 – Nail in E. Side
- 16) 13" Maple S32°W 29.5
- 17) 10" Oak S60°W 41.4

WASHTENAW ENGINEERING, N.N. Fahrner
 #17620, 11/17/94, Survey R-6819

- 18) Power pole North 52.90 to Nail
- 19) 11" Walnut N60°E 48.52 Tto Nail
- 14) 15" Walnut S25°E 27.13 to Nail
- 15) Power pole South 23.28 to Nail
- 16) 20" Oak S25°W 29.69 to Nail



Peggy M. Haines - Washtenaw Co. CORREM

Copy

RECEIVED SECTION

2000

SECTION