

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Washtenaw (County) Located In: Corner Code #

1. Public Land Survey T 2S R 5E J-9
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling in Section S ___ T ___ R ___
 S ___ T ___ R ___

3. Miscellaneous Property in Section S ___ T ___ R ___
 S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____



5094734
Page: 1 of 2
02/07/2000 02:55P
L-2 P-339

Peggy M. Haines - Washtenaw Co. CORREM
Copy Register of Deed Stamp & File Nurr

I, Thomas L. Sutherland, in a field survey on 11-8-1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent resortation: 13

- G.L.O. 1819, Field Notes
- 1) 18" W.O. N11°W 85 Links
- 2) 21" W.O. N88°W 130 Links

- H.H. Atwell #322, No Date, Grid Book
- Iron Pipe
- 3) 18" Cherry S54°E 50.6
- 4) 12" Cherry S4°E 46.8
- 5) 14" B. Oak S68 1/2°E 74.7

Continued on Back

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found PK Nail Stub in chiselled hole of concrete drive apron

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Stub of broken PK nail in chiseled hole of concrete drive apron
- 8) 34" Chinese Elm S45°W 41.55 to remon tag on NW Side
- 10) NE Corner of porch (Conc. Block) S35°W 70.03
- 14) Guy pole S60°E 51.97 to remon tag on SW Side
- 15) Power pole S5°E 28.92 to remon tag on W. Side
- 16) 6" Locust S20°E 51.30 to remon tag on E. Side
- 17) Top center of hydrant S85°E 91.38
- 18) S. Edge concrete/N. Edge asphalt South 14.73
- 19) Edge of metal at expansion joint N5°E 10.76

I conclude after careful study of the record documentation and field observation, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by: Thomas L. Sutherland Date: 12/17/99
 Surveyor's Michigan License No. 24620
 THOMAS L. SUTHERLAND
 No. 24620

APPROVED
DATE 12/6/99
CO. REP. KX



SECTION

Continued

Washtenaw Engineering, C.C. Wilson #13604 6/25/74,
L.C.R.C. Liber 4, Page 103; Survey R-3295

- 1" Iron Pipe
- 5) 30" B. Oak S68 1/2°E 74.9 to nail
- 5) S. Edge of pavement N'y 12.5
- 7) Power pole S'y 27.50 to nail
- 8) 12" Chinese Elm N45°W 41.60 to nail

Control Survey Associates, J.N. Owens #20709, 4/75,
Survey 2S5E23-75-47; R.T. Tietsema # 20712, 3/78,
Survey 30-78-2S5E23

- 9) Pipe North 68.22
- 5) 36" Oak S65°E 74.92
- 10) Porch Cor. S35°W 70.07

Atwell-Hicks, 9/9/77, Survey 505-40

- 1" Iron Pipe
- 5) 30" B. Oak S68 1/2E 74.9 to nail
- 6) S. Edge of pavement N'y 12.5
- 7) Power pole S'y 27.50 to nail
- 8) 12" C. Elm N45°W 41.60 to nail

McNamee, Porter and Seeley, Arvin Butterfield #21561,
2/23/78, L.C.R.C. Liber 5, Page 17.

Found 1/8" Dia. Concrete nail - set a lead plug with
chiseled "X" at same location as concrete nail. "Talked
to party chief from Atwell-Hicks Inc. He stated that he
witnessed the iron just before the curb was installed over
it. Then he set a concrete nail in the gutterpan according
to his witnessess. He stated the iron pipe is still below the
curb and gutter"

- 5) 30" B. Oak S68 1/2°E 74.90 to nail
- 7) Power pole S'y 27.40 to nail
- 8) 12" Chinese Elm N45°W 41.9
- 11) Back of curb South 1.4

Washtenaw Engineering, N.N. Fahrner # 17620 3/27/80,
L.C.R.C. Liber 6, Page 11; 4/1/80, Survey R-4585

- Chisel Hole in Curb cut of gutter
- 5) 30' B. Oak S68 1/2°E 74.90 to nail
- 6) S. Edge pvt North 12.50
- 7) Power pole South 27.50 to nail
- 8) 12" Chinese Elm S 45°W 41.60 to nail
- 12) N. Edge gutter pan North 0.44
- 11) S. Edge gutter South 1.52

Washtenaw Engineering; N.N. Fahrner #17620 7/8/86,
Survey R-5461

- Nail in Gutter
- 13) Power pole S05°E 24.76 to nail
- 8) 12" Chinese Elm S45°W 41.60 to nail
- 12) North Edge of gutter North 0.44
- 11) South Edge of gutter South 1.52

Midwestern Consulting, A.R. Rentschler
#15411, 2/13/89, Survey 89029; 8/7/90, Survey 90140

- P.K. Nail in Lead Plug
- 11) Back of Curb 1.55 South
- 7) U.P South 27.50
- 5) 30" B.O. S68°E 74.90

Midwestern Consulting, D.M. Bongiovanni #24586, 4/8/91,
L.C.R.C. Liber 7, Page 277; A.R. Rentschler #15411, 7/10/96,
Survey 96164; P.L. Hastings #37277, 9/27/96, Survey 96153

- P.K. Nail in Concrete gutter
- 5) Nail in 30" Oak S68E 74.93
- 13) PK in W/Side P.P. South 25.70
- 14) PK in SW/Side guy pole S60°E 52.00
- 8) PK in NW/Side 18" Ash S50°W 41.45

Land Surveying Consultants, R.T. Tietsema #20712, 2/97,
Survey 00997-2S5E26

- P.K. Nail in Concrete Drive
- 13) Util. Pole South 25.70
- 14) Guy Pole S60°E 52.00
- 8) 18" Ash S50°W 41.45