




A. Continued

W.C.R.C., W.J. Armstrong #2444, 5/1/32, Grid Book  
From J.B. Davis witness tree found the trace of an old wood  
stake in the center of a pile of stones and bricks. Reset with  
iron pipe, stones, and bricks.

- 3) S.W. corner stone porch N30 1/2°E 126.4
- 4) 4" Apple S57°W 49.2
- 5) 18" Hickory N37°W 94.0
- 6&7) 2 Right of Way Pipes



5094736  
Page: 2 of 2  
02/07/2000 02:55P  
L-2 P-344

W.C.R.C., No Date, Grid Book (handwritten)

- 8) Guard Post N75°W 74.20 to Nail
- 9) E. Pole S69°W 77.29 to Nail

W.C.R.C., No Date, Grid Book (handwritten - Lodi Twp.  
Witnesses)

- 10) N. 1/4 Lodi Twp. is 54.4 East of S1/4 Post Sec. 35  
Scio Township

Atwell-Hicks, Taft, 4/29/56

Found 1 1/2" Iron 2' Deep. Set 1/2" iron pipe on top  
6" below surface

- 5) N39°W 93.6 to 15" Hickory
- 11) N66°W 52.4 to 10" Elm
- 12) N8°E 44.7 to 6" Pine

Atwell-Hicks, R.J. Jagow # 6998, 7/23/75

L.C.R.C., Liber 4, page 33 - P.V. Schwimmer #24618,  
8/20/77, Survey 505-38

- 1/2" Rerod in monument box
- 10) N 1/4 Cor. Sec 2 E'ly 50.31
- 12) 14" Blue Spruce N18°E 44.7
- 13) 12" Twin C. Elm North 49.8
- 5) 18" Shag Hickory N40°W 93.6

Washtenaw Engineering, N.N. Fahrner #17620 5/27/81,  
L.C.R.C., Liber 6, Paage 151 - T.L. Sutherland #24620,  
6/2/81, Survey R-4735

- 1/2" Iron pipe in monument box
- 5) 18" Hickory N37°W 94.0
- 9) Power pole S69°W 77.29 to Nail
- 12) 12" Pine N10°E 44.49 to Nail

Ayres, Lewis, Norris, and May, C.C. Wilson # 13604,  
9/20/85, Survey 82252-01

- 1/2" Iron rod in monument box
- 12) 14" Blue Spruce N18°E 44.7
- 13) 12" Elm N'ly 49.8
- 5) 18" Shag Hickory N40°W 93.6

Land Surveying Consultants, R.T. Tietsiema # 20712,  
9/4/87, Survey 13-03687-2S5E35

- 5) 16" Hickory N39°W 93.6
- 11) 12" Elm N66°W 52.4
- 12) 9" Pine N08°E 44.7

Washtenaw Engineering, N.N. Fahrner #17620 5/16/97,  
Survey R7376

- 3/4" Rod in monument box
- 12) 18" Pine N10°E 44.44 to Nail
- 14) 8" Box Elder N10°W 24.55 to Nail
- 10) N 1/4 Cor. Sec. 2, Lodi Twp East 54.26

REM  
SECTION