

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &  
 REMONUMENTATION**

NOV 02 1999

for corners in  
Washtenaw  
 (County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

SECTION \_\_\_\_\_

1. Public Land Survey T 2S R 5E \_\_\_\_\_ K-2 \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_



**5017331**  
 Page: 1 of 2  
 02/25/1999 02:59P  
**L-2 P-226**

Register of Deed Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Thomas L. Sutherland, in a field survey on, 11/21/98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent resortation:

- G.L.O., 1815 Field Notes  
 1) 27" WO S35°E 16 Links  
 2) 24" BO N30°W 70 Links

(Continued on other side)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found Bent 1" Iron Pipe in North-South Fence Line and 1.3 North of Remnants of fence line to the East. Reset 1" Iron Pipe with Aluminum Remonumentation Cap stamped 24620.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1" x 24" Iron Pipe with Remonumentation Cap stamped 24620  
 3) 14" Hickory S87°E 5.84 to Remon tag on North Side—  
 4) 12" Hickory S87°E 24.8  
 5) 18" Hickory South 14.65 to Remon Tag on E. Side  
 6) 18" Hickory S85°W 21.64 to Remon Tag on S. Side  
 8) 3" Thornapple N15°E 6.80 to Remon Tag on East Side  
 9) R.R. Tie Fence Post South 1.89 to Remon Tag on E. Side

APPROVED  
 DATE 12-14-98  
 CO. REP. KA

I conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by: Thomas L. Sutherland  
 Surveyor's Michigan License No. 24620



12-21-98

**COPY**

SURVEY &  
REMONUMENTATION

NOV 02 1999

SECTION

A. (Continued from Front)

W.C.R.C. W.J. Armstrong #2444, 10/20/36 Grid Book

- 3) Hickory 6" S87°E 6.05
- 4) Hickory 5" S87°E 25.2
- 5) Hickory 6" South 14.6
- 6) Hickory 8" S85°W 21.4



5017331

Page: 2 of 2

02/25/1999 02:59P

Peggy M. Haines - Washtenaw Co. CORREM L-2 P-227

Robert L. Smith #16052, 5-74, L.C.R.C. L3, P529

- 1" Iron Pipe at Anchor Post
- 3) East 5.70 Nail in 10" Maple
- 6) West 21.80 Nail in 18" Oak
- 5) South 14.40 Nail in 15" Oak

Washtenaw Engineering, N. Fahrner #17620, 9/8/77, L.C.R.C. L4, P324; 9/13/77,  
Dwg. R-4006; 9/1/81, Dwg. R-4739

Iron Pipe

- 3) 12" Hickory S87°E 6.05
- 4) 8" Hickory S87°E 25.2
- 5) 12" Hickory South 14.6
- 6) 14" Hickory S85°W 21.4

Atwell-Hicks, R. Jagow Jr. 33137, Dwg 507-171

1" Iron Pipe

- 3) 14" Hickory Nail S. Side S87°E 6.05
- 4) 10" Hickory Nail S. Side S87°E 25.2
- 5) 14" Hickory Nail W. Side South 14.6
- 6) 18" Hickory Nail N. Side S85°W 21.4
- 7) Centerline Fence Post for N-S-E Fence Line South 1.3

- copy -