

NOV 02 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

corners in
Washtenaw
(County)

Located In:

Corner Code #



5017334
Page: 1 of 2
02/25/1999 02:59P
L-2 P-232

Peggy M. Haines - Washtenaw Co. CORREM

copy

Register of Deed Stamp & File Number

Public Land Survey

T ___ R ___
T ___ R ___
T ___ R ___
T ___ R ___

Property Controlling
in Section

S 1 T 2S R 5E L-1
T ___ R ___

Miscellaneous
Property in Section

S ___ T ___ R ___
S ___ T ___ R ___

Lot No. _____, Recorded Plat _____

Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Thomas L. Sutherland, in a field survey on, 11/13/98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent resortation:

W.C.R.C., W.J. Armstrong #2444, Grid Book, - found old wood stake. Set iron pipe.
Iron Pipe
1) 4" Hickory N731/2°E 4.6
2) 8" Hickory S70°E 21.1
3) 1 1/2" Hickory S40°W 8.6
4) 5" Wild Plum N84°W 29.3
(Continued on other side)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" Iron Rod inside 2" Iron Pipe or axle inside gear or sprocket. Sprocket or gear was 6" to 8" below ground surface. Placed Remon Tag over Rod.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Remon Tag over 1/2" Iron Rod inside 2" Iron Pipe, inside gear or sprocket (gear or sprocket was 6" to 8" below ground)
1) 16" Hickory N73°E 4.57 to Remon Tag on N.W. Side
2) 20" Hickory S70°E 21.19 to Remon Tag on N. Side
5) Telephone Pole West 14.10 to Flasher N. Side
6) Power Pole N10°W 40.53 to Remon Tag on E. Side
7) 14" Stump (12'High) S80°W 26.17 to Remon on Tag N. Side
8) S.W. Corner of Garage N57°E 59.91
9) 6" Well N05°E 22.79

APPROVED
DATE 12-14-98
CO: REP. *KA*

This corner is 0.64 North of the Township Line.
This corner is not common to L-13, T1S, R5E.

I conclude that after careful study of the record documentation and field observations, that this corner was not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Signed by: *Thomas L. Sutherland*
Surveyor's Michigan License No. 24620
No. 24620



12-21-98 COPY

SURVEY &
REMONUMENTATION

NOV 02 1999

SECTION

A. (Continued from Front)

Atwell-Hicks, R.J. Jagow #6998
6/19/78, Dwg. 507-87

- 5) Power Pole Westerly 14.3
- 6) Power Pole N10°W 40.4
- 7) 8" Elm S80°W 26.8



5017334

Page: 2 of 2

02/25/1999 02:59P

Peggy M. Haines - Washtenaw Co. CORREM L-2 P-233

-copy

Washtenaw Engineering, N. Fahrner #17620
11/10/78, L.C.R.C. L-5, P148

Iron Pipe

- 1) 14" Hickory N73°E 4.6
- 2) 18" Hickory S70°E 21.1
- 5) Telephone Pole West 14.14 to Nail
- 8) SW Corner Garage N35°E 60.00