

MAY 09 1996

- Copy -

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Washtenaw</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28</u> R <u>5E</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED
WASHTENAW COUNTY, MI
MAR 29 1 59 PM '96
REGISTER OF DEEDS STAMP & FILE NUMBER

Thomas L. Sutherland in a field survey on October 10, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | | | |
|---------------|---------------|----------------|----|-----------------------------|
| Unknown | Field Notes | Unknown | 1) | 40" W. Oak N14°W 32 Links |
| G.L.O. | | | 2) | 17" B. Oak S06°W 27 Links |
| October, 1922 | Survey 803-54 | 3/4" Iron Pipe | 3) | 8" Hickory N60°E 6.7 |
| H.H. Atwell | | and Stones | 4) | 12" Basswood EAST 18.1 |
| | | | 5) | 7" Basswood EAST 30.4 |
| | | | 6) | 12" Hickory WEST 24.2 |
| | | | 7) | 10" Triple W. Oak W'ly 34.2 |
| | | | 8) | 20" Basswood WEST 55.4 |
| | | | 9) | 2" Hickory S75°W 13.4 |

(SECTION A. CONTINUED ON REVERSE SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

All Witnesses were destroyed during construction of I-94. The position of the corner was determined by surveying Pinewood Street right-of-way, a part of "THE EVERGREENS" and projecting it South to the North line of Section 25 as platted.

*Old Witness Found

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I conclude that after careful study of the record documentation and field observations, that this corner is accepted as a careful and faithful reestablishment of the position of the original corner.

Set 3/4" Iron Pipe W/W.G.R.F. Cap
1.9 North of South Edge Asphalt
Shoulder of Eastbound I-94 Expressway

- | | |
|---|--|
| 10) NW Corner Lot 39 "THE EVERGREENS" N07°28'53"E 830.50 to Iron Pipe | 14) 14" Pine N25°00'28"W 168.2 to Tag in NE Side |
| 11) SE Corner Lot 82 "THE EVERGREENS" N11°46'14"E 216.08 to Iron Pipe | 15) Power Pole N16°35'24"E 175.2 to Tag in W'ly Side |
| 12) 14" Elm S15°29'07"W 73.01 to Tag in W'ly Side | 16) Center of Hydrant N24°41'20" 225.99 |
| 13) 12" Walnut S54°20'17"E 183.00 to Tag in SW Side | |

Signed by Thomas L. Sutherland
Surveyor's Michigan License No. #24620

Date December 11, 1995

*Old Witness Found

- Copy -

(CONTINUED FROM A. ON FRONT)

Unknown H.H. Atwell	Grid Book (W.C.R.C.)	Iron Pipe	3) 4) 6) 9)	8" Hickory N60°E 6.7 12" Basswood EAST 18.1 12" Hickory WEST 24.2 2" Hickory S75°W 13.4
August, 1951 M.S.H.D.	Grid Book (W.C.R.C.)	Unknown	3) 4) 6) 9)	12" Hickory N60°E 6.7 32" Basswood EAST 18.1 15" Hickory WEST 24.2 5" Hickory S75°W 13.4
November 18, 1963 M.S.H.D.	Sheet 74, Washtenaw County Right- of-Way Book	Unknown	None	

*Old Witness Found

APPROVED
DATE 11/6/95
CO. REP. FX