

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

NOV 02 1999

SECTION

or corners in  
Washtenaw  
(County)

Located In: Corner Code #

Public Land Survey T 2S R 5E M-2

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_



*Copy* Register of Deed Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Thomas L. Sutherland, in a field survey on November 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent resortation:

G.L.O. 1815 Field Notes  
1) 9" Elm N2°E 65 Links  
  
(Continued on Other Side)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" Iron Pipe 2.5 West of East edge of gravel, .5 below gravel surface inside, 2 1/2" Iron Pipe 1.2 below gravel surface surrounded by bricks and rocks 1.5 below gravel surface. Set Aluminum Remonumentation Cap stamped 24620 over 1/2" Iron Pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1) Remonumentation Cap stamped 24620 over 1/2" Iron Pipe (.5 below gravel surface and 2.5 West of East Edge gravel) over 2 1/2" Iron Pipe surrounded by bricks and rocks.
- 2) 12" Stump N65°E 16.48 to Spike on SE Side
- 3) Twin 12"-8" Hickory S51°W 45.88 to Remon Tag on E. Side
- 4) 24" Stump S56°W 34.38 to nail on SE Side
- 5) 26" Oak S35°E 32.16 to Remon Tag on SW Side
- 6) 16" Cherry N55°W 42.60 to Remon Tag on NE Side
- 7) 28" Ash N25°W 80.23 to Remon Tag on NE Side
- 8) A-2, T2S, R6E North 172.47

APPROVED  
DATE 12-14-98  
CO. REP. KA

This Corner is not common to A-2, T2S, R6E.

I conclude that after careful study of the record documentation and field observations, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by: Thomas L. Sutherland  
Surveyor's Michigan License No. 24620

12-21-98 COPY

A. (Continued from Front)

W.C.R.C., W.J. Armstrong #2444 9/10/36 Grid Book

Iron Pipe, Stones and Bricks

- 2) Elm 36" N23°E 49.3
- 3) B. Cherry 4" N65°E 16.5
- 4) Forked Elm 6" S17°E 26.8
- 5) Twin Hickory 5" S51°W 45.9
- 6) Basswood 6" S56°W 34.4



5017336

Page: 2 of 2

02/25/1999 02:59P

L-2 P-237

Peggy M. Haines - Washtenaw Co. CORREM

- copy -

Washtenaw Engineering, N. Fahrner #17620

12/21/76, Dwg. R-3854 and L.C.R.C. L4, P300

1/2" Iron Pipe

- 2) 36" Dead Elm N23°E 49.3
- 3) 9" Cherry N65°E 16.5
- 5) 9" Twin Hickory S51°W 45.9
- 6) 24" Basswood S56°W 34.4
- 7) 20" Oak S45°E 9.5

SURVEY &  
REMONUMENTATION

NOV 02 1999

SECTION

Washtenaw Engineering, N. Fahrner #17620

11/10/78, L.C.R.C. L5, P149; 11/15/78 Dwg. R-4260; 11/16/78 Dwg. R4262; 3/31/79

Dwg. R-4347; 11/6/80 Dwg. R-4670

1/2" Iron Pipe

- 2) 36" Dead Elm N23°E 49.3
- 3) 9" Dead Cherry N65°E 16.5
- 5&6) 9" Twin Hickory S56°W 34.4
- 7) 20" Oak S45°E 9.5