

REF

2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Washtenaw  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 2S R 5E

I-5

Cooy-

T R

T R

T R

2. Property Controlling  
in Section

S

T R

S

T R

3. Miscellaneous  
Property in Section

S

T R

S

T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_



5094721  
Page: 1 of 2  
02/07/2000 02:55P

Peggy M. Haines - Washtenaw Co. CORREM

L-2 P-314

Register of Deed Stamp & File Number

I, Thomas L. Sutherland, in a field survey on 11/15/99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent resortation:

G.L.O., 1819, Field Notes

- 1) 26" W.O. S25°W 5 Links
- 2) 20" W.O. N45°E 12 Links

Continued on Back

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" threaded rod 4" below gravel surface over 1/2" x 20" iron pipe. Removed existing pipe and rod and set 1" x 24" pipe with aluminum remonumentation cap stamped 24620 6" below gravel surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" x 24" iron pipe with aluminum remonumentation cap stamped 24620 6" below gravel surface.

- 3) 20" Walnut S75°E 31.62 to remon tag on S'ly side
- 8) 30" Ash N30°E 58.87 to remon tag on W'ly side
- 9) 19" Oak S45°E 70.64 to remon tag on SW side
- 11) 12" Oak N15°W 64.72 to remon tag on W'ly side
- 12) Power pole (DE64-40G5) West 25.41 to PK on N. Side
- 13) Twin 11"-13" Ash East 45.79 to remon tag on N. Side
- 16) MBT Pole S20°E 62.08 to PK on W'ly side

I conclude after careful study of the record documentation and field observation, that this corner is accepted as the best available evidence of the position of the original corner.

Signed by:

*Thomas L. Sutherland*

THOMAS L.  
SUTHERLAND

Date

12/17/99

Surveyor's Michigan License No. 24620

No. 24620

APPROVED

DATE 12/13/99

CO. REP. *Ky*

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

