

SURVEY & REMONUMENTATION

MAY 09 1996

COMMISSION

Liber 00001 Page 0463 RM

- Copy -

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Washtenaw (county)	Located In:	Corner Code #
1. Public Land Survey	T 2S R 6E	C-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED
 WASHTENAW COUNTY, MI
 MAR 29 1 36 PM '96
 PERRY A. JAMES
 COUNTY CLERK/REGISTER
 - COPY -

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, R.T. Tietsema, in a field survey on 12/17, 19 95, do hereby certify that under the requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

Date	Owner	Job No.	Fl'd. Notes	Set Original Corner	Monument	Direction	Distance
12/12/1815	GLO				1) 18" Ash 2) 8" Sugar	N21W S73E	16 links (10.56') 17 links (11.22')
6/13/1932	W.J. Armstrong		WCRC Grid Book	Fnd Iron bar with pieces of tile and stone around it. Reset with an Iron Pipe, stones, and bricks	3) 8" Elm 4) 10" W. Oak 5) 1" B. Oak 6) 12" Sycamore 7) 6" W. Oak 8) 6" Hickory 9) 30" Elm 10) NE Cor Sec 6 T3S, R6E	SE S82E NLY S46.5W S68W SLY SLY East	33.0' 4.0' 49.7' 49.5' 9.2' 33.9' 33.3' 59.4
9/26/1974	Robert J. Jaglow	6998	Boundary	Fnd. 3/4" Iron. Pipe in mon. box	11) 12" Burr Oak 12) Mon Box 13) 4" Ash 14) 6" Ash 15) 4" Crabapple	N40W East S15E S20W S45E	52.3' 59.0' 72.2' 72.9' 56.6'
5/2/1975	Robert J. Jaglow	6998	Boundary	Fnd. 3/4" Iron. Pipe in mon. box	11) 12" Burr Oak 12) Mon Box 13) 4" Ash 14) 6" Ash 15) 4" Crabapple	N40W East S15E S20W S45E	52.3' 59.0' 72.2' 72.9' 56.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd. 1/2" Iron. Rod in mon. box
 Also found remaining witnesses:

11) 16" Burr Oak	N40W	52.32' to nail in E. side
12) Iron rod in mon box	East	59.0'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" iron Pipe with Remonumentation Cap in mon. box
 Set additional accessories:

16) Twin Ash (10", 6")	N05E	32.12' to nail in E side
17) Utility Pole	S30E	87.45' to nail W side
18) Sign Post	S20E	31.42'

APPROVED
 DATE 12/11/95
 CO. REP. [Signature]

It is my opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

Signed by [Signature] Date 18 Dec. 95
 Surveyor's Michigan License No. 20712