

SURVEY & REMONUMENTATION

Liber 000001 Page 0464 RM

MAY 09 1996

COMMISSION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Washtenaw</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>6E</u>	<u>D-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTERED
 WASHTENAW COUNTY, MI
 MAR 29 1 36 PM '96
 REG. M. HAINES
 COUNTY CLERK/REGISTER
 COPY -

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, R.T. Tietsema, in a field survey on 12/17, 1995, do hereby certify that under the requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

1817	GLO	Fld. Notes	Set Original Corner	1) 6" Ironwood	N80W	30 links (19.80')
				2) 6" Ironwood	S16E	27 links (17.82')
Unknown		WCRC Grid Book	Find Iron Stake	3) 22" Elm	S60W	45.35'
				4) 12" Hickory	N45W	41.7'
				5) 10" Maple	N86W	59.8'
				6) 14" Apple	N87E	79.0'
				7) 12" Maple	S87.5E	85.8'
				8) N 1/4 Post Section 5 T3S, R6E	East	191.8'
12/26/40		WCRC Grid book	Rewitnessed	8) N 1/4 Post Section 5 T3S, R6E	(Distance revised when rewitnessed) East	141.7'
				9) 14" Walnut	NW	107.2'
				10) 2" Spruce	East	42.0'
				11) 8" Elm	NE	76.2'
				12) 14" Hickory	NW	106.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Iron Pipe in Mon Box
 None of the previous witnesses still existed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Cap on existing 1" Iron Pipe in Mon Box
 Set additional accessories:

13) Walk/Don't Post	65W	69.54'
14) NE Bolt at Base of Traffic Light Pole	45W	62.75'
15) SW Bolt at Base of Traffic Light Pole	N70E	28.57'
16) P. Pole	S30E	72.03' to nail in SW side

APPROVED
 DATE 12/11/95
 CO. REP. KJ

Signed by [Signature] Date 18 Dec. 95
 Surveyor's Michigan License No. 20712