

**SURVEY &
REMONUMENTATION**

Liber **00001** Page **0465** *RN*

MAY 09 1996

- Copy -

COMMISSION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED
 WASHTEENAW COUNTY, MI
 MAR 29 1 37 PM '96
 COUNTY CLERK/REGISTRAR
 - COPY -

For corners in

<u>Washtenaw</u> (county)	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>6E</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, R.T. Tietsema, in a field survey on 12/7, 1995, do hereby certify that under the requirements of P.A.74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

1817	GLO	Fld. Notes	Set Original Corner	1) 8" Ash 2) 16" Hickory	S80W S63E	9 links (5.94') 30 links (19.80')
February, 1924	H.H. Atwell No Job No, No Client listed	Sketch of Survey	Rectangular Iron Bar	3) NE Corner Barn 4) NE Corner Hse 5) 6" Elm 6) 8" Cherry 7) 6" Evergreen 8) 24" Butternut 9) NE Cor Hse 10) NW Cor Hse same 11) 7" Maple	SW SE S80E SLY SE SE SLY SLY N10E	77.8' 43.2' 60.0' 3.0' 47.5' to cen 44.6' to cen 45.9' 43.6' not to back shed part of hse 126.45'
1/18/1984	Arvin N. Butterfield JOB NO: 1463, 1464 & 1465	Boundary	Fnd. 3/4" Iron Pipe	4) NE Corner Hse. 12) SE Corner Hse #1720 13) SW Corner Hse #1720 14) 20" Cherry	S20E N15E N45W N40E	45.2' 40.7' 36.45' 45.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Iron Pipe.
 Also found remaining accessories:

4) NE Corner Hse #2008 S. State	S20E	45.20'
12) SE Corner Hse #1720 S. State	N15E	40.70'
13) SW Corner Hse #1720 S. State	N45W	36.45'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Cap on existing 3/4" Iron Pipe.
 Set additional accessories:

15) 3/4" Iron Pipe	East	29.84'
16) U. Pole	East	38.55' nail in SW side
17) 18" Pine	S25E	45.70' nail in W side
18) W. edge Sidewalk	East	30.50'

APPROVED
 DATE 12/11/95
 CO. REP. [Signature]

It is my opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

Signed by [Signature] Date 18 Dec. 95
 Surveyor's Michigan License No. 20712