

**SURVEY &
REMONUMENTATION**

MAY 09 1996
COMMISSION

Liber 000001 Page 0466 RW

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

- Copy -
RECORDED
WASHTENAW COUNTY, MI
MAR 29 1 38 PM '95
PERCIVAL JAMES
COUNTY CLERK/REGISTRAR

For corners in

Washtenaw (county)	Located In:	Corner Code #
1. Public Land Survey	T 2S R 0E	H-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- COPY -

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, R.T. Tietsema, in a field survey on 12/7, 1995, do hereby certify that under the requirements of P.A.74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with the regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

Date	Owner	Boundary	Monument	Distance
1817	GLO	Field Notes	Set Original Corners	1) 30" W. Oak S25E 61 links (40.26') Set quarter post 2) 18" W. Oak N15E 32 links (21.12')
Unknown	Unknown	WCRC Grid book	Pipe in Fence intersection with rocks around it	Centerline of Pvmf/ North 72.0'
5/17/1954	Atwell-Hicks JOB NO: 2421	Boundary	3) N 1/4 Corner Section 3 T3S, R6E	East 206.01'
1/3/1955	Atwell-Hicks, Inc.	Plat of "Ann Arbor Woods" (L12P38)	3) N 1/4 Corner Section 3 T3S, R6E	East 206.01'
6/3/1955	Atwell-Hicks, Inc. JOB NO: 4544	Boundary	4) SW Lot Cor	S01-20-00W 60.01 to sec cor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Iron Pipe 0.5' N & 0.5' W of fence corner
Also found remaining witnesses:

3) N 1/4 Corner Section 3 T3S, R6E Fnd 1/2" Iron Pipe	East	205.82'
4) 1 1/2" Iron Pipe SW Lot Corner	North	60.04'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" Iron Pipe over existing 1/2" Iron Pipe and set Remonumentation Cap
Set additional accessories:

5) 18" Box Elder	N45E	8.60
6) Utility Pole	West	14.11'
7) 15" Locust	S45W	22.08'
8) Triple Box Elder (15", 6" 6")	West	7.65'

APPROVED
DATE 12/11/95
CO. REP. KX

It is my opinion that this corner represents the original corner and is accepted as the best available evidence of the position of the original corner.

Signed by R. T. Tietsema Date 18 DEC. 95
Surveyor's Michigan License No. 20712