

APPROVED

DATE 11-20-96

CC. REC. KA

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich, P.A. 1970

RECORDED
WASHTENAW COUNTY, MI
FEB 18 9 08 AM '97
PEGGY K. HAINES
COUNTY CLERK/REGISTER

For corner in
Washtenaw
(County)

Located in: Corner Code #

1. Public Land Survey	T <u>2S</u>	R <u>6E</u>	<u>I-11</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec	S _____	T _____	R _____
	S _____	T _____	R _____

Liber 00001 Page 0597R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Charles C. Wilson, in a field survey on November 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instruction of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

United States Government Survey, 1815 Instructions, Surveyed 1819
 Bearing Trees W. Oak 23" N48deg.E 17.16'
 W. Oak 38" N57-1/2deg.W 47.52'
 Meas. (N) 2640'
 (S) 2640'
 (E) 2585.55'
 (W) 2591.16'

Continued on Back:

SURVEY & REMONUMENTATION

MAY 15 1997

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Iron Pipe in center of Thorn Bush Clump across from driveway at House #2997 Devonshire from information and accessories mentioned in Paragraph A.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Re-Set 3/4" Iron Pipe with a 1" x 24" Iron Pipe with Remonumentation Cap Stamped #13604
 24" Cherry S20deg.E 16.67' (Nail & RT W/S) ****
 Quadruple Walnut S80deg.W 40.89' (Nail & RT E/S) **
 18" Walnut S30deg.W 38.33' (Nail & RT E/S) ***
 Twin 16"-20" Cherry S5deg.W 75.8' *
 14" Oak S5deg.W 38.79' (Nail & RT W/S) *
 SW'ly Bolt in Base of Light Pole N35deg.W 134.60' *
 * Indicates accessory previously mentioned in Paragraph A.
 RT Indicates Remonumentation Tag

I believe this point should be accepted as the best available evidence of the position of the original corner. This point was ratified by the Washtenaw County Peer Committee on November 20, 1996

Signed by Charles C. Wilson
Surveyors Michigan's License No. 13604

Date November 21, 1996

COPY



